

SCREENING SITE INSPECTION REPORT
FOR
CHEVRON USA INC CINCINNATI ASPHALT REF
NORTH BEND, OHIO
U.S. EPA ID: OHDO83364679
SS ID: NONE
TDD: F05-8804-005
PAN: FOH0556SB

US EPA RECORDS CENTER REGION 5



504448

OCTOBER 3, 1991

This Draft Screening Site Inspection Report is considered confidential and pre-decisional in nature. Material and information contained within this report may not be released without the approval of the United States Environmental Protection Agency Region V Pre-Remedial Unit.



ecology and environment, inc.

111 WEST JACKSON BLVD., CHICAGO, ILLINOIS 60604, TEL. 312-663-9415

International Specialists in the Environment

recycled paper

SIGNATURE PAGE
FOR
SCREENING SITE INSPECTION REPORT
FOR
CHEVRON USA INC CINCINNATI ASPHALT REF
NORTH BEND, OHIO
U.S. EPA ID: OHD083364679
SS ID: NONE
TDD: F05-8804-005
PAN: FOH0556SB

Prepared by: Scott A. Turek Date: 10/11/91
Scott A. Turek
FIT Report Preparer
Ecology and Environment, Inc.

Reviewed by: Robert Kurzeja for BK Date: 10/11/91
Robert Kurzeja
FIT State Coordinator
Ecology and Environment, Inc.

Approved by: Kathleen D. Oskvarek for JDO Date: 10/11/91
Jerome D. Oskvarek
FIT Office Manager
Ecology and Environment, Inc.

TABLE OF CONTENTS

<u>Section</u>		<u>Page</u>
1	INTRODUCTION.....	1-1
2	SITE BACKGROUND.....	2-1
	2.1 INTRODUCTION.....	2-1
	2.2 SITE DESCRIPTION.....	2-1
	2.3 SITE HISTORY.....	2-1
3	SCREENING SITE INSPECTION PROCEDURES AND FIELD OBSERVATIONS.....	3-1
	3.1 INTRODUCTION.....	3-1
	3.2 SITE REPRESENTATIVE INTERVIEW.....	3-1
	3.3 RECONNAISSANCE INSPECTION.....	3-2
	3.4 SAMPLING PROCEDURES.....	3-5
4	ANALYTICAL RESULTS.....	4-1
5	DISCUSSION OF MIGRATION PATHWAYS.....	5-1
	5.1 INTRODUCTION.....	5-1
	5.2 GROUNDWATER.....	5-1
	5.3 SURFACE WATER.....	5-4
	5.4 AIR.....	5-5
	5.5 FIRE AND EXPLOSION.....	5-5
	5.6 DIRECT CONTACT.....	5-5
6	REFERENCES.....	6-1

Table of Contents (Cont.)

<u>Appendix</u>		<u>Page</u>
A	SITE 4-MILE RADIUS MAP.....	A-1
B	U.S. EPA FORM 2070-13.....	B-1
C	FIT SITE PHOTOGRAPHS.....	C-1
D	U.S. EPA TARGET COMPOUND LIST AND TARGET ANALYTE LIST QUANTITATION/DETECTION LIMITS.....	D-1
E	SOIL BORING LOGS OF THE AREA OF THE SITE.....	E-1
F	WELL LOGS OF THE AREA OF THE SITE.....	F-1

LIST OF FIGURES

<u>Figure</u>		<u>Page</u>
2-1	Site Location.....	2-2
3-1	Site Features.....	3-3
3-2	Soil/Sediment Sampling Locations.....	3-6
3-3	Monitoring and Production Well Sampling Locations.....	3-8

LIST OF TABLES

<u>Table</u>		<u>Page</u>
4-1	Results of Chemical Analysis of FIT-Collected Soil/Sediment Samples for the Chevron Asphalt Site SSI.....	4-2
4-2	Results of Chemical Analysis of FIT-Collected Production Well Samples for the Chevron Asphalt Site SSI.....	4-5

1. INTRODUCTION

Ecology and Environment, Inc., Field Investigation Team (FIT) was tasked by the United States Environmental Protection Agency (U.S. EPA) to conduct a screening site inspection (SSI) of the Chevron USA Inc Cincinnati Asphalt Ref (Chevron Asphalt) site under contract number 68-01-7347.

The site was discovered on April 14, 1982, when U.S. EPA received a Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) 103(c) form (U.S. EPA Form 8900-1) from Chevron U.S.A., Inc. (Chevron).

The site was evaluated in the form of a preliminary assessment (PA) that was submitted to U.S. EPA. The PA was prepared by Claudine F. Jones of the Ohio Environmental Protection Agency (OEPA), Southwest District Office, and is dated December 2, 1987 (U.S. EPA 1987).

FIT prepared an SSI work plan for the Chevron Asphalt site under technical directive document (TDD) F05-8804-005, issued on April 4, 1988. The SSI work plan was approved by U.S. EPA on August 20, 1990. The SSI of the Chevron Asphalt site was conducted on October 10 and 11, 1990, under amended TDD F05-8804-005, issued on August 24, 1990.

The FIT SSI included an interview with site representatives, a reconnaissance inspection of the site, and the collection of 10 soil/sediment samples and 1 production well sample.

The purposes of an SSI have been stated by U.S. EPA in a directive outlining Pre-Remedial Program strategies. The directive states:

All sites will receive a screening SI to 1) collect additional data beyond the PA to enable a more refined preliminary HRS [Hazard Ranking System] score, 2) establish priorities among sites most likely to qualify for the NPL [National Priorities List], and 3) identify the most critical data requirements for the listing SI step. A screening SI will not have rigorous data quality objectives (DQOs). Based on the refined preliminary HRS score and other technical judgement factors, the site will then either be designated as NFRAP [no further remedial action planned], or carried forward as an NPL listing candidate. A listing SI will not automatically be done on these sites, however. First, they will go through a management evaluation to determine whether they can be addressed by another authority such as RCRA [Resource Conservation and Recovery Act].... Sites that are designated NFRAP or deferred to other statutes are not candidates for a listing SI.

The listing SI will address all the data requirements of the revised HRS using field screening and NPL level DQOs. It may also provide needed data in a format to support remedial investigation work plan development. Only sites that appear to score high enough for listing and that have not been deferred to another authority will receive a listing SI. (U.S. EPA 1988)

U.S. EPA Region V has also instructed FIT to identify sites during the SSI that may require removal action to remediate an immediate human health or environmental threat.

2. SITE BACKGROUND

2.1 INTRODUCTION

This section presents information obtained from SSI work plan preparation, the site representative interview, and the reconnaissance inspection of the site.


2.2 SITE DESCRIPTION

The Chevron Asphalt site is a 95-acre parcel of land, situated on a 133-acre property. The site, which is composed of two sections separated by the Baltimore and Ohio (B & O) Railroad tracks, contains an active asphalt processor and a storage facility. The site is located at 11001 Brower Road, in a mixed rural and residential area, approximately 4 miles southwest of North Bend, Hamilton County, Ohio (N1/2 sec. 35 and SW1/4 sec. 36, T.2, F.R.1) (see Figure 2-1 for site location). The site is approximately 1 mile east-northeast of the junction of the Ohio River and the Great Miami River.

A 4-mile radius map of the Chevron Asphalt site is provided in Appendix A.

2.3 SITE HISTORY

The Chevron Asphalt site primarily functions as an asphalt terminal. The site receives finished liquid asphalt (AC-20) from a Chevron refinery located near Pascagoula, Mississippi (Raatz 1985; Chevron [no date]). The site also accepts asphalt from producers other than Chevron subsidiaries (Kittle 1990). Operations at the Chevron Asphalt site include the processing and/or transferring of three asphalt products--



SOURCE: USGS, Lawrenceburg, KY-IN-OH Quadrangle, 7.5 Minute Series, 1961; Hooven, OH-IN-KY Quadrangle, 7.5 Minute Series, 1954, photorevised 1970.




FIGURE 2-1 SITE LOCATION

paving asphalt, emulsion asphalt, and shingle asphalt (Baxter et al. 1990).

The Chevron Asphalt site was not developed prior to 1954. In July 1954, American Bitumuls and Asphalt Company (ABSC), which was a subsidiary of Standard Oil Company of California (SOCC), acquired the Chevron Asphalt site and established an asphalt refinery on-site. Between 1954 and 1970, the name of the subsidiary was changed from ABSC to Cincinnati Asphalt Terminal. In approximately 1970, SOCC changed its corporate name to Chevron U.S.A., Inc. (Chevron) (Baxter et al. 1990).

Asphalt, fuel oil, and naphtha were refined at the site (Raatz 1985). A lagoon was excavated on-site to serve as a gravity separator for oil and water and to contain any spills from an adjacent large storage tank. In the 1950s, Chevron constructed a new oil/water separator within the lagoon. Since then, Chevron has used the lagoon for gravity separation of oil and water only during periods when the facility requirements have exceeded the capacity of the new oil/water separator (Raatz 1985).

In 1965, refining processes were discontinued at the Chevron Asphalt site (Chevron [no date]; Raatz 1985; Halbleib 1982). In the 1970s, the Chevron Asphalt site served as the location for the district office of the Asphalt Division of Chevron (Baxter et al. 1990).

There are two operating production wells on-site. These wells were drilled by Moody's of Dayton, Inc. One or more test-type production wells were also installed on-site. These wells were closed after the drinking water quality was demonstrated to be unimproved over the drinking water quality of existing wells (Kittle 1990). In 1979, an ammonia/nitrate plume was detected in groundwater from the production wells, and the origin of the plume was believed to be from an off-site source (Hemker 1990). The use of production wells on-site for drinking water purposes was discontinued because of the ammonia/nitrate contamination. Bottled water was obtained and transported by truck from the city of Cleves, Ohio. From 1979 to 1989, 12 monitoring wells were installed in conjunction with 3 assessment studies (Geraghty & Miller Hydrocarbon Services [no date]). These monitoring wells are sampled quarterly (Baxter et al. 1990).

In 1982, Chevron began to phase out operational activities at the lagoon. Chevron modified the lagoon and used it only for the containment of storage tank spills. A new oil/water separator, consisting of a concrete tank with an oil/water separating device called a skimmer, was constructed south of the lagoon. Spent process water from the lagoon was routed through pipes to this oil/water separator. The oil recovered from the separator is recycled into the production processes (Kittle 1990). The continuously flowing effluent from the skimmer was channeled to a National Pollution Discharge Elimination System-permitted outfall (identified as outfall 001) that discharges into Dark Hollow Creek (Baxter et al. 1990).

Chevron petitioned U.S. EPA to have the sludge in the lagoon delisted as hazardous material when sampling conducted by Chevron proved that it was nonhazardous (Raatz 1985). However, U.S. EPA continued to consider the sludge in the lagoon as being hazardous and refused to delist it. Chevron withdrew the petition in 1985 and the sludge remains in the lagoon.

From 1980 to 1983, on-site spills of asphalt, gasoline, and #2 heating oil at the Chevron Asphalt site were documented (U.S. EPA 1987). The majority of the spills occurred during deliveries and transfers at the site (Baxter et al. 1990). Materials are delivered to the site via truck, rail, and barge (Chevron [no date]).

The Chevron Asphalt site has a storage tank capacity of nearly 1.2 million barrels. The site receives 700,000 to 800,000 barrels of hot asphalt a year at its barge terminal (Chevron [no date]). Site operations generate 1,000 barrels of waste per year, most of which is off-specification material. Normally, such material can be recycled into paving asphalt, emulsion asphalt, or shingle asphalt. Unrecoverable residue and office waste are transported by Rumpke, of Cincinnati, Ohio. Four waste shipments per year, with a total volume of 156 cubic yards, are sent to a landfill (Baxter et al. 1990).

According to FIT file information, no other regulatory or response actions have been taken at the Chevron Asphalt site.

3. SCREENING SITE INSPECTION PROCEDURES AND FIELD OBSERVATIONS

3.1 INTRODUCTION

This section outlines procedures and observations of the SSI of the Chevron Asphalt site. Individual subsections address the site representative interview, reconnaissance inspection, and sampling procedures. Rationales for specific FIT activities are also provided. The SSI was conducted in accordance with the U.S. EPA-approved work plan with the following exceptions. Sediment samples were not collected along the Ohio River because no appropriate sampling locations could be determined at the time of the SSI. Only one of the two production wells was sampled because both wells draw from approximately the same depth.

The U.S. EPA Potential Hazardous Waste Site Inspection Report (Form 2070-13) for the Chevron Asphalt site is provided in Appendix B.

3.2 SITE REPRESENTATIVE INTERVIEW

Dennis Palmer, FIT team leader, conducted an interview with Ralph Baxter, Operations Supervisor; L. D. Turley, Refinery Manager; Don Kittle, Maintenance Supervisor, all of Chevron, and Dan L. Hemker, Project Engineer of the Superfund Site Management Unit from the San Francisco office of Chevron. The interview was conducted on October 10, 1990, at 9:00 a.m. in a conference room on-site. Deborah Hallock of FIT was also present during the interview. The interview was conducted to gather information that would aid FIT in conducting SSI activities.

3.3 RECONNAISSANCE INSPECTION


Following the site representative interview, FIT conducted a reconnaissance inspection of the Chevron Asphalt site and surrounding area in accordance with Ecology and Environment, Inc. (E & E), health and safety guidelines. The reconnaissance inspection began at 10:40 a.m. and included a walk-through of the site to determine appropriate health and safety requirements for conducting on-site activities and to make observations to aid in characterizing the site. FIT also determined sampling locations during the reconnaissance inspection. FIT was accompanied by Kittle and Hemker during the reconnaissance inspection.

Reconnaissance Inspection Observations. The Chevron Asphalt site consists of two sections, a northern section and a southern section, separated by B & O Railroad tracks (see Figure 3-1 for site features). The northern section is bordered on the north by Brower Road and a county park, on the east by a rail yard and an inactive industrial facility, on the south by the railroad tracks and a power plant, and on the west by Station Avenue. The southern section is bordered on the north by the railroad tracks, the rail yard, and the inactive industrial facility, on the east by trees, on the south by the Ohio River, and on the west by the power plant.

Dark Hollow Creek flows through the northern section and part of the southern section of the site. The creek begins north of the site as two branches in the county park north of Brower Road and then merges within the site boundaries. The branches are identified as the northwest and northeast branches. The creek exits the site through the northwest corner of the southern section and flows through the power plant property before entering the Ohio River.

An access road connects the northern and southern sections with a bridge over Dark Hollow Creek. The access road runs through the middle of the southern section to a barge terminal on the Ohio River.

The northern section of the site contains the facility's offices, the boiler house and furnace system, and the majority of the aboveground storage tanks at the site. The northern section measures 48 acres and contains 12 buildings (Baxter et al. 1990). The southern section contains 6 large storage tanks partially surrounded by a berm and an area



SOURCE: Drawn from map by Harbeston, 11-17-88.




FIGURE 3-1 SITE FEATURES

of stressed vegetation. No buildings are located in this section, which consists of 47 acres (Hemker 1990).

Active operations at the Chevron Asphalt site are conducted in the south-central portion of the northern section. The southern area of this portion contains a loading facility for trucks, an administrative office building, a maintenance building, and a laboratory. A boiler house and a furnace system are north of this area. Numerous overhead pipes cross the access road, and various types and sizes of storage tanks are located west and southwest of the boiler house. The two operating production wells are located just north of the railroad tracks. One of the wells is identified as the south well (Kittle 1990). The other well is identified as the west well (Hemker 1990; Halbleib 1982).

A large storage tank and a lagoon are located in the east-central part of the northern section. The lagoon is approximately 300 feet long and 100 feet wide and is of unknown depth. The lagoon is located between the large storage tank to the west and crescent-shaped lagoon walls to the east. FIT site-entry equipment (the OVA) detected readings that deviated from background near the lagoon.

An outfall (outfall 001) is located on the eastern side of the northern section. This outfall leads from the currently used oil/water separator located south of the lagoon to Dark Hollow Creek, into which it discharges. The flow from outfall 001 is from an open culvert that is connected to the oil/water separator.

The northern section of the site appears to be completely fenced. A woodland is located in the northern portion of this section.

Six large storage tanks in the southern section of the site are located east of the access road. These tanks are surrounded by a berm on the east, south, and west sides, and by a railroad grade on the north side. An area of stressed vegetation lies between the access road and the west side of the berm. Just south of the railroad tracks are pipelines that connect the six storage tanks to the processing facilities in the northern section.

The barge terminal is located in the southern portion of the southern section of the site, on the Ohio River. The terminal is used during the spring and summer for asphalt transfer (Kittle 1990).

FIT photographs from the SSI of the Chevron Asphalt site are provided in Appendix C.

3.4 SAMPLING PROCEDURES


Samples were collected by FIT at locations selected during the reconnaissance inspection to determine whether U.S. EPA Target Compound List (TCL) compounds or Target Analyte List (TAL) analytes were present at the site. The TCL and TAL are included with corresponding quantitation/detection limits in Appendix D.

On October 10, 1990, FIT collected 10 soil/sediment samples, including a potential background sample, and 1 production well sample. Portions of on-site soil/sediment and production well samples were offered to site representatives by FIT. Two soil sample portions and a production well sample portion were accepted by representatives of the Chevron Asphalt site.


Soil/Sediment Sampling Procedures. Sediment sample S1 was collected off-site from the northeast branch of Dark Hollow Creek, approximately 50 feet east of the northern section's fence (see Figure 3-2 for soil/sediment sampling locations). Sample S1 was collected as an upstream sample to determine the representative chemical content of the creek sediment upstream of the site. Sediment sample S2 was collected off-site from the east bank of Dark Hollow Creek approximately 150 feet north of the junction of the creek and the Ohio River. Sample S2 was collected to determine whether TCL compounds or TAL analytes were migrating from the site to the creek.

Sediment sample S3 was collected from the edge of the lagoon in the northern section of the site. Surface soil sample S4 was collected approximately 10 feet northwest of sampling location S3. Samples S3 and S4 were collected to determine whether TCL compounds and TAL analytes were present in the soil or sediment in the lagoon area.

Sediment sample S5 was collected from the east bank of Dark Hollow Creek approximately 15 feet south of the bridge that crosses the creek. Sample S5 was collected to determine whether TCL compounds or TAL analytes were migrating from the site to the creek. Surface soil sample S6 was collected halfway between sampling location S2 and the southwest corner of the berm. Sample S6 was collected to determine whether TCL



SOURCE: Drawn from map by Harbeston, 11-17-88.



LEGEND
▲ SOIL ▼ SEDIMENT

FIGURE 3-2 SOIL/SEDIMENT SAMPLING LOCATIONS

compounds or TAL analytes may have migrated overland toward the creek. Surface soil sample S7 was collected from the area of stressed vegetation within the berm. Subsurface soil sample S8 was collected from within the berm with a posthole digger and hand auger at a depth of 2 to 4 feet. Water was encountered at a depth of 1 1/2 feet and the soil was clay-like at depth. Samples S7 and S8 were collected to determine whether TCL compounds or TAL analytes were present in the bermed area.

Surface soil sample S9 was collected approximately 300 feet east of sampling location S8, from a vegetated area near the storage tanks. Sample S9 was collected to determine whether any spills from the tanks or other on-site operations have occurred in the area.

Surface soil sample S10 was collected as a potential background sample from a grassy area east of the bermed area. Sample S10 was collected to determine the representative chemical content of the soil in the area of the site.

All surface soil/sediment samples were collected with garden trowels. The sample portions collected for volatile organic analysis were transferred directly to sample bottles. The remaining sample portions were placed into a stainless steel bowl, mixed, and then transferred to the appropriate sample bottles, using a stainless steel spoon or a hand trowel (E & E 1987).

Standard E & E decontamination procedures were adhered to during the collection of all soil/sediment samples. The procedures included the scrubbing of all equipment (e.g., trowels, spoons, bowls, posthole digger, and hand auger) with a solution of detergent (Alconox) and distilled water, and triple-rinsing the equipment with distilled water before the collection of each sample (E & E 1987). All soil/sediment samples were packaged and shipped in accordance with U.S. EPA-required procedures.

As directed by U.S. EPA, all soil/sediment samples were analyzed using the U.S. EPA Contract Laboratory Program (CLP).

Production Well Sampling Procedures. Production well sample PW1 was collected on-site from the south well (see Figure 3-3 for monitoring and production well sampling locations). The south well is 110 feet deep.

All production well samples were obtained from an outlet that bypassed water treatment systems and storage tanks. Water was allowed to discharge from the outlet for 20 minutes before samples were collected to ensure that the sample source had been purged of standing water (E & E 1987). In accordance with U.S. EPA quality assurance/quality control requirements, a duplicate production well sample and a field blank sample were collected. The duplicate sample was collected at location PW1. The field blank sample was prepared from distilled water.

As directed by U.S. EPA, all production well samples were analyzed using the U.S. EPA CLP.

4. ANALYTICAL RESULTS

This section presents results of the chemical analysis of soil/sediment and production well samples collected by FIT during the SSI of the Chevron Asphalt site. All samples were analyzed for volatile organics, semivolatile organics, pesticides/polychlorinated biphenyls (PCBs), metals, and cyanide. Complete chemical analysis results of FIT-collected soil/sediment and production well samples are provided in Tables 4-1 and 4-2. In addition, significant tentatively identified compounds (TICs) detected in the analysis of FIT-collected samples are also provided in Table 4-1.

Quantitation/detection limits used in the analysis of FIT-collected samples are provided in Appendix D.

The analytical data from the chemical analysis of FIT-collected samples for this SSI have been reviewed under the direction of U.S. EPA for validity; the review has been approved by U.S. EPA. The analytical data have also been reviewed by FIT for usability. Any additions, deletions, or changes resulting from review of the data have been incorporated in the chemical analysis results tables presented in this section.

Table 4-1
RESULTS OF CHEMICAL ANALYSIS OF
FIT-COLLECTED SOIL/SEDIMENT SAMPLES FOR THE CHEVRON ASPHALT SITE SSI

Sample Collection Information and Parameters	S1	S2	S3	S4	S5	Sample Number S6	S7	S8	S9	S10
Date	10/10/90	10/10/90	10/10/90	10/10/90	10/10/90	10/10/90	10/10/90	10/10/90	10/10/90	10/10/90
Time	1300	1200	1300	1315	1415	1400	1400	1430	1530	1500
CLP Organic Traffic Report Number	EKW69	EKW70	EKW71	EKW72	EKW73	EKW74	EKW75	EKW76	EKW77	EKW78
CLP Inorganic Traffic Report Number	MEKD69	MEKD70	MEKD71	MEKD72	MEKD73	MEKD74	MEKD75	MEKD76	MEKD77	MEKD78
<u>Compound Detected</u> (values in µg/kg)										
<u>Volatile Organics</u>										
methylene chloride	59J	15J	29J	--	--	54J	--	--	17	--
acetone	--	--	120J	--	--	--	--	--	--	--
chloroform	3J	--	--	--	--	--	--	--	--	--
1,2-dichloroethane	2J	--	--	--	--	--	--	--	--	--
bromodichloromethane	5J	--	--	--	--	--	--	--	--	--
toluene	--	--	--	--	--	--	27J	--	50	--
chlorobenzene	2J	--	--	--	--	--	--	--	--	--
xlenes (total)	--	--	--	--	--	20J	--	--	7	--
<u>Semivolatile Organics†</u>										
phenanthrene	230J	530J	100J	--	230J	290J	220J	--	R	--
anthracene	--	160J	--	--	170J	--	--	--	R	--
di-n-butylphthalate	87J	--	96J	--	--	110J	89J	140J	R	92J
fluoranthene	390J	740J	280J	210J	410J	480J	810J	--	R	--
pyrene	350J	590J	270J	190J	410J	410J	910J	--	R	--
benzo[a]anthracene	180J	340J	140J	120J	200J	280J	470J	--	R	--
chrysene	260J	500J	180J	140J	440J	390J	630J	--	R	--
bis(2-ethylhexyl)phthalate	--	--	--	--	--	--	--	--	R	--
benzo[b]fluoranthene	170J	520J	180J	130J	360J	310J	530J	--	R	--
benzo[k]fluoranthene	90J	390J	110J	120J	190J	250J	290J	--	R	--
benzo[a]pyrene	150J	430J	170J	140J	240J	240J	470J	--	R	--
indeno[1,2,3-cd]pyrene	--	260J	120J	--	140J	110J	210J	--	R	--
benzo[g,h,i]perylene	--	230J	130J	--	120J	--	250J	--	R	--
<u>Pesticides/PCBs†</u>										
<u>TICs††</u>										
dodecane, 2-methyl-6-propyl (55045-08-4)	--	--	--	--	3,000J	--	--	--	R	--
undecane, 3,6-dimethyl (17301-28-9)	--	--	--	--	2,000J	--	--	--	R	--
hexacosane (630-01-3)	--	--	--	--	3,000J	--	--	--	R	--

Table 4-1 (Cont.)

Sample Collection Information and Parameters	Sample Number									
	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10
dodecane, 2,6,11-trimethyl (31295-56-4)	--	--	--	--	2,000J	--	--	--	R	--
tetratetracontane (7098-22-8)	--	--	--	--	1,000J	--	--	--	R	--
<u>Analyte Detected</u> (values in mg/kg)										
aluminum	3,610	10,600	5,690	7,910	6,380	12,500	12,300	13,200	9,220	11,500
antimony	--	--	--	20.5NJ	25.3NJ	22.8NJ	--	32.7NJ	--	22.3NJ
arsenic	5.9NJ	10.7NJ	8.6NJ	15.4NJ	7NJ	12.3NJ	10.4NJ	9.6NJ	5.9NJ	7NJ
barium	35.1B	77.7	57.5B	67.5	52.1B	206	116	194	145	177
beryllium	0.34B	0.85B	0.55B	0.6B	0.52B	1.5	1B	1.4	0.97B	1.1B
cadmium	--	--	0.82BNJ	1.6NJ	1BNJ	1.8NJ	--	0.63BNJ	--	0.92BNJ
calcium	46,200	16,800	1,460B	3,070	11,100	2,940	1,510	2,010	2,340	1,850
chromium	11.8	26.5	35.8	32.5	20	46.4	19.7	22.1	15.6	21.9
cobalt	9.6B	14.8B	6.9B	9.1B	9.2B	27.2	15.5	17.2	13.4	15.1
copper	146NAJ	48NAJ	36.4NAJ	35.2NAJ	29.4NAJ	50.5NAJ	783NAJ	29.3NAJ	21.6NAJ	26.5NAJ
iron	17,200	26,100	15,300	23,000	17,500	33,000	29,200	37,800	21,800	26,300
lead	39.7	44.8NJ	33.7	34NJ	29.6	74.7	22.6NJ	30.4NJ	22.1NJ	30.6NJ
magnesium	8,260	5,390	1,160B	2,150	3,620	2,690	2,460	2,740	2,260	2,410
manganese	595	792	287	407	458	1,400	941	1,150	923	1,080
mercury	--	--	0.2	--	0.19	0.29	--	--	--	--
nickel	14.8J	33.3	17.3J	21.9	20.8	54.9	24.5	32	23.7	29.8
potassium	554B	1,340B	885B	1,070B	913B	1,400	1,190B	1,490	1,000B	1,410
selenium	--	--	--	--	--	0.57B	--	--	--	--
silver	--	1.4B	--	--	--	1.8B	1.1B	1.3B	0.87B	0.75B
sodium	230B	367B	183B	126B	186B	124B	123B	199B	127B	113B
thallium	--	--	--	--	--	0.86BNJ	--	--	--	--
vanadium	11.6B	24	23.3	23.3	16.6	25.4	27.3	29.7	20.9	24.3
zinc	79.3	151	87.2	88.2	99.2	313	70.8	82.7	63.3	103

-- Not detected.

† The semivolatile organic, pesticide/PCB, and TIC fractions of sample S9 have been qualified R.

†† TIC Chemical Abstracts Service (CAS) numbers, if available, are provided in parentheses.

Table 4-1 (Cont.)

COMPOUND QUALIFIERS	DEFINITION	INTERPRETATION
J	Indicates an estimated value.	Compound value may be semiquantitative.
R	Results are unusable due to a major violation of QC protocol.	Compound value is not usable.
X	Cannot be confirmed by CLP protocols.	Compound may or may not be present.
ANALYTE QUALIFIERS	DEFINITION	INTERPRETATION
N	Spike recoveries outside QC protocols, which indicates a possible matrix problem. Data may be biased high or low. See spike results and laboratory narrative.	Value may be quantitative or semiquantitative.
A	Duplicate value outside QC protocols which indicates a possible matrix problem.	Value may be quantitative or semiquantitative.
B	Value is real, but is above instrument DL and below CRDL.	Value may be quantitative or semiquantitative.
J	Value is above CRDL and is an estimated value because of a QC protocol.	Value may be semiquantitative.
M	Duplicate injection precision not met.	Value may be semiquantitative.
W	Post-digestion spike for furnace AA analysis is out of control limits (35-115%), while sample absorbance is <50% of spike absorbance.	Value may be semiquantitative.
R	Results are unusable due to a major violation of QC protocols.	Analyte value is not usable.

Table 4-2
RESULTS OF CHEMICAL ANALYSIS OF
FIT-COLLECTED PRODUCTION WELL SAMPLES FOR THE CHEVRON ASPHALT SITE SSI

Sample Collection Information and Parameters	PW1	Sample Number	
		Duplicate	Blank
Date	10/10/90	10/10/90	10/10/90
Time	1530	1530	1510
CLP Organic Traffic Report Number	EKW65	EKW67	EKW68
CLP Inorganic Traffic Report Number	MEKD65	MEKD67	MEKD68
Temperature (°C)	11	11	11
Specific Conductivity (µmhos/cm)	4,100	4,100	5.5
pH	NA	NA	NA
<u>Compound Detected</u>			
(values in µg/L)			
<u>Volatile Organics</u>			
methylene chloride	4J	4J	4J
chloroform	—	—	0.9J
2-butanone (MEK)	R	R	R
<u>Analyte Detected</u>			
(values in µg/L)			
aluminum	55BJ	63.3BJ	58.5B
barium	104B	104B	—
calcium	141,000	141,000	196BJ
cobalt	7.6B	5.2B	—
iron	176J	296J	—
lead	—	2.1BNWJ	5.4N
magnesium	37,500	37,300	37.4B
manganese	22.1	20.9	—
potassium	5,390	5,620	—

Table 4-2 (Cont.)

Sample Collection Information and Parameters	PW1	<u>Sample Number</u>	
		Duplicate	Blank
sodium	29,800EJ	30,000EJ	652BEJ
zinc	7.7B	15.3B	--
<p>NA Not available.</p> <p>-- Not detected.</p>			

Table 4-2 (Cont.)

COMPOUND QUALIFIERS	DEFINITION	INTERPRETATION
J	Indicates an estimated value.	Compound value may be semiquantitative.
R	Results are unusable due to a major violation of QC protocol.	Compound value is not usable.
ANALYTE QUALIFIERS	DEFINITION	INTERPRETATION
E	Estimated or not reported due to interference. See laboratory narrative.	Analyte or element was not detected, or value may be semiquantitative.
N	Spike recoveries outside QC protocols, which indicates a possible matrix problem. Data may be biased high or low. See spike results and laboratory narrative.	Value may be quantitative or semiquantitative.
B	Value is real, but is above instrument DL and below CRDL.	Value may be quantitative or semiquantitative.
J	Value is above CRDL and is an estimated value because of a QC protocol.	Value may be semiquantitative.
W	Post-digestion spike for furnace AA analysis is out of control limits (35-115%), while sample absorbance is <50% of spike absorbance.	Value may be semiquantitative.

5. DISCUSSION OF MIGRATION PATHWAYS

5.1 INTRODUCTION

This section presents discussions of data and information pertaining to potential migration pathways and targets of TCL compounds and TAL analytes that are possibly attributable to the Chevron Asphalt site.

The five migration pathways of concern discussed are groundwater, surface water, air, fire and explosion, and direct contact.

5.2 GROUNDWATER

FIT collected one groundwater sample. The sample, PW1, was collected from an on-site production well. TCL compounds and TAL analytes were detected at low levels in sample PW1.

TCL compounds and TAL analytes were detected in on-site soil samples, including acetone (120J $\mu\text{g/kg}$ in sample S3), toluene (50 $\mu\text{g/kg}$ in sample S9), xylenes (total) (20J $\mu\text{g/kg}$ in sample S6), copper (783N*J mg/kg in sample S7), and mercury (0.29 mg/kg in sample S6) (definitions and interpretations of qualifiers are provided in Table 4-1). These TCL compounds and TAL analytes are attributable to the site because they were detected at levels above those detected in the background samples.

A potential does exist for TCL compounds and TAL analytes to migrate from the site to groundwater, based on the following information.

- TCL compounds and TAL analytes were detected at levels above background in on-site soil/sediment samples.

- Industrial wastes were deposited in the lagoon and have not been removed (Baxter et al. 1990).
- No liner exists at the lagoon.
- On-site spills of asphalt, gasoline, and heating oil were documented.

The potential for TCL compounds and TAL analytes to migrate to groundwater is also based on the following geologic and hydrogeologic information.

The geology in the area of the site consists of alluvium-containing unconsolidated sands, clays, and gravels that extend to bedrock consisting of Ordovician-age Eden Shale and Limestone (Bownocker 1981). The Great Miami Buried Valley (Great Miami) aquifer, which is a federally designated sole source aquifer, is located beneath the site. Groundwater in the Great Miami aquifer flows toward the southwest, and has a pumping rate in excess of 1,000 gallons per minute (Regional Council of Governments 1988).

According to area soil boring logs, the geology beneath the site consists of alternating layers of clay and gravel to a depth of approximately 33 to 44 feet. The clay and gravel overlie sand and gravel, which is present at a depth of approximately 58 to 99 feet (see Appendix E for soil boring logs of the area of the site). According to area well logs, the Ordovician-age bedrock is present at a depth of approximately 81 feet below ground surface (see Appendix F for well logs of the area of the site). Well logs also indicate that significant layers of clay exist in the unconsolidated deposits. These clay layers are not continuous; however, they may retard the vertical migration of water. Beyond the lacustrine deposits from the Ohio and Great Miami rivers, limestone and dolomite bedrock is exposed at the surface. Because there is no continuous confining layer of clay throughout a 3-mile radius of the site, the unconsolidated deposits and the bedrock form the aquifer of concern (AOC). Private wells in the area of the site are finished in the unconsolidated deposits.

The majority of the residents within a 3-mile radius of the Chevron Asphalt site obtain their drinking water from private and municipal wells that draw from the AOC. The 3-mile radius of the Chevron Asphalt site includes portions of three states: Ohio, Indiana, and Kentucky. The nearest residential well is located approximately 8/10 miles from the site. The population potentially affected by the migration of TCL compounds and TAL analytes from the site to groundwater includes those residents in Ohio, Indiana, and Kentucky who use private residential wells as their source of drinking water. Residents of Cleves and North Bend, Hamilton County, Ohio, who reside within a 3-mile radius of the site receive drinking water from the Cleves municipal water system (Meves 1990), which consists of four municipal wells located outside a 3-mile radius of the site. Therefore, the population that resides within a 3-mile radius of the site that is served by the Cleves municipal water system is not included in the potential target population. Residents of Lawrenceburg, Indiana, who reside within a 3-mile radius of the site obtain their drinking water from the Lawrenceburg municipal water system (Horney 1990). However, these residents are not included in the potential target population because the three municipal wells that supply the city of Lawrenceburg are located outside a 3-mile radius of the Chevron Asphalt site.

In Hamilton County, Ohio, approximately 379 persons obtain drinking water from private wells located within a 3-mile radius of the Chevron Asphalt site. This population was calculated by the counting the houses located in Hamilton County within a 3-mile radius of the site, but outside municipal water service boundaries, on United States Geological Survey (USGS) topographic maps of the area of the site (USGS 1954, 1961, 1961a, 1982) and multiplying this number by the persons-per-household value of 2.65 for Hamilton County, Ohio (U.S. Bureau of the Census 1982).

All persons in Boone County, Kentucky, who reside within a 3-mile radius of the site draw water from private wells. The population potentially affected by the migration of TCL compounds and TAL analytes to groundwater in Boone County, Kentucky, is approximately 338 persons. This population was calculated by counting the number of houses located in Boone County within a 3-mile radius of the site on USGS topographic

maps of the area of the site (USGS 1954, 1961, 1961a, 1982) and multiplying this number by the persons-per-household value of 3.07 for Boone County, Kentucky (U.S. Bureau of the Census 1982).

In Dearborn County, Indiana, approximately 574 persons obtain drinking water from private wells located within a 3-mile radius of the site. This population was calculated by counting houses in Dearborn County within a 3-mile radius of the site, but outside municipal water service boundaries, on USGS topographic maps of the area of the site (USGS 1954, 1961a) and multiplying this number by the persons-per-household value of 2.96 for Dearborn County, Indiana (U.S. Bureau of the Census 1982).

The total population in Ohio, Indiana, and Kentucky potentially affected by the migration of TCL compounds and TAL analytes from the site to groundwater is approximately 1,291 persons.

5.3 SURFACE WATER

The body of surface water nearest to the site is Dark Hollow Creek, which crosses the site. The Great Miami River flows into the Ohio River approximately 1 mile downstream from the site.

TCL compounds and TAL analytes were detected in sediment samples collected from Dark Hollow Creek and the on-site lagoon. Most of the TCL compounds and TAL analytes detected in the downstream sediment samples were detected at levels similar to those detected in the upstream sediment sample, S1. The TAL analyte mercury, detected at 0.19 mg/kg in downstream sediment sample S5, is attributable to the site because it was not detected in the upstream sediment sample. Mercury was also detected at levels above background in an on-site soil sample and the sediment sample from the lagoon.

A potential does exist for TCL compounds and TAL analytes to migrate from the site to surface water, based on the following information.

- Sediment sample S5 was collected from Dark Hollow Creek, which flows through the site and empties into the Ohio River.

- On-site spills of asphalt, gasoline, and heating oil were documented.

There are no surface water intakes located within 3 miles downstream of the site (Simpson 1991; Rudolph 1990). The Ohio River is used for recreational purposes (Connet 1990).

5.4 AIR

A release of TCL compounds or TAL analytes to the air was not documented during the SSI of the Chevron Asphalt site. During the reconnaissance inspection, FIT site-entry instruments (combination explosimeter/oxygen meter and colorimetric monitoring tubes for hydrogen cyanide) did not detect levels that deviated from background concentrations at the site. However, the OVA detected organic vapors at ground level that deviated from background at one location, in the basin of the lagoon. In accordance with the U.S. EPA-approved work plan, further air monitoring was not conducted by FIT.

A potential does not exist for TCL compounds and TAL analytes to migrate from the site via windblown particulates because most of the site is covered with vegetation.

5.5 FIRE AND EXPLOSION

According to federal, state, and local file information reviewed by FIT, and a telephone conversation with Don Heinrich, Fire Chief, North Bend, Ohio, no documentation exists of an incident of fire or explosion at the site (Heinrich 1990). According to FIT observations and site-entry equipment readings, no potential for fire or explosion existed at the site at the time of the SSI.

5.6 DIRECT CONTACT

According to federal, state, and local file information reviewed by FIT, observations made during the SSI, and the interview with site representatives, no incidents of direct contact with TCL compounds or TAL analytes at the Chevron Asphalt site have been documented. However, a potential does exist for the general public to come into direct

contact with TCL compounds and TAL analytes detected on-site, based on the following information.

- TCL compounds and TAL analytes were detected in on-site surface soil samples.
- The site is not completely fenced. There is no fencing around the southern part of the site.

The population within a 1-mile radius of the site potentially affected through direct contact with TCL compounds and TAL analytes at the site is 70 persons. This population was calculated by counting houses within a 1-mile radius of the site on USGS topographic maps (USGS 1954, 1961) and multiplying this number by a persons-per-household value of 2.65 for Hamilton County, Ohio, and 3.07 for Boone County, Kentucky (U.S. Bureau of the Census 1982).

6. REFERENCES

- Baxter, Ralph, L. D. Turley, and Don Kittle, October 10, 1990, Operations Supervisor, Refinery Manager, and Maintenance Supervisor, respectively, all of Chevron, and Dan L. Hemker, Project Engineer, Superfund Site Management Unit, Chevron, San Francisco, interview, conducted by Dennis Palmer of E & E.
- Bownocker, J. A., 1981, Geologic Map of Ohio, Department of Geological Survey, Ohio Department of Natural Resources.
- Chevron, no date, brochure intended for public relations activities, produced by Asphalt Division, Chevron.
- Connet, Mel, May 4, 1990, Water Department, Covington, Kentucky, telephone conversation, contacted by Jennifer Dubay of E & E.
- E & E, 1987, Quality Assurance Project Plan Region V FIT Conducted Site Inspections, Chicago, Illinois.
- Geraghty & Miller Hydrocarbon Services, no date, portion of a site assessment study submitted to Chevron.
- Halbleib, Michael, April 14, 1982, Environment Compliance Specialist, Chevron, Louisville, Kentucky, Notification of Hazardous Waste Site form, (U.S. EPA Form 8900-1), to U.S. EPA, Region V, Chicago, Illinois.

Heinrich, Dan, June 15, 1990, Fire Chief, Miami Township #1 Volunteer Fire Department, North Bend, Ohio, telephone conversation, contacted by Dennis Palmer of E & E.

Hemker, Dan L., October 10, 1990, Project Engineer, Superfund Site Management Unit, Chevron, San Francisco, comments to FIT staff during SSI.

Horney, Roland, March 1, 1990, Supervisor, Lawrenceburg Utility Department, telephone conversation, contacted by Karen Sadler of E & E.

Kittle, Don, October 10, 1990, Maintenance Supervisor, Chevron, comments to FIT staff during SSI.

Meves, Beverly, May 22, 1990, Clerk, Cleves Water Department, telephone conversation, contacted by Casey Lawal of E & E.

Raatz, S. G., September 1, 1985, Environmental Compliance Specialist, Chevron, Louisville, Kentucky, delisting petition (No. 0394) for lagoon bottom material, to Barbara Bush, Environmental Toxicologist, Waste Identification Branch (WH-562), U.S. EPA, Washington, D.C.

Regional Council of Governments, March 1988, Ohio-Kentucky-Indiana, Petition for Sole Source Aquifer Designation of the Great Miami Buried Valley Aquifer System in Butler, Clermont, Hamilton, and Warren Counties, Ohio.

Rudolph, Frank, June 6, 1990, Director, Greendale Utilities, Lawrenceburg, Indiana, telephone conversation, contacted by Dennis Palmer of E & E.

Simpson, Jim, February 14, 1991, Supervisor, Water Pollution Control Unit, Southwest District Office, OEPA, telephone conversation, contacted by Dennis Palmer of E & E.

U.S. Bureau of the Census, 1982, 1980 Census of Population, Characteristics of the Population, General Population Characteristics, Ohio, Indiana, Kentucky, Washington, D.C.

U.S. EPA, December 2, 1987, Potential Hazardous Waste Site Preliminary Assessment, for the Chevron Asphalt site, U.S. EPA ID: OHD083364679, prepared by William Poole of E & E, September 3, 1986, revised by Claudine F. Jones, OEPA, December 2, 1987.

_____, February 12, 1988, Office of Solid Waste and Emergency Response, Pre-Remedial Strategy for Implementing SARA, Directive number 9345.2-01, Washington, D.C.

USGS, 1954, photorevised 1970, Hooven, Ohio-Indiana-Kentucky Quadrangle, 7.5 Minute Series: 1:24,000.

_____, 1961, photorevised 1969 and 1974, Burlington, Indiana Quadrangle, 7.5 Minute Series: 1:24,000.


_____, 1961a, Lawrenceburg, Kentucky-Indiana-Ohio Quadrangle, 7.5 Minute Series: 1:24,000.

_____, 1982, photorevised 1987, Addyston, Ohio-Kentucky Quadrangle, 7.5 Minute Series: 1:24,000.

7206:9

APPENDIX A

SITE 4-MILE RADIUS MAP



- CLEVES WATER DISTRIBUTION BOUNDARY
- GREENDALE WATER DISTRIBUTION BOUNDARY
- LAWRENCEBURG WATER DISTRIBUTION BOUNDARY

ecology and environment inc.
111 WEST JACKSON BLVD., CHICAGO, ILLINOIS 60604
International Operations in the Environment

USGS TOPOGRAPHIC MAPS

NAME	DATE	REVIS
GUILFORD	1966	1983
AURORA	1981	
HOOVEN	1954	1970
LAWRENCEBURG	1961	
ADDYSTON	1982	1987
BURLINGTON	1961	1969, 1974

SCALE 1:24,000

CONTOUR INTERVAL 10 FT.

QUADRANGLE LOCATION

KENTUCKY

APPENDIX B

U.S. EPA FORM 2070-13



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
OH D083364679

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site) Chevron USA Inc. - Cincinnati Asphalt Ref		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER 11001 Brower Road			
03 CITY North Bend	04 STATE OH	05 ZIP CODE 45052	06 COUNTY Hamilton	07 COUNTY CODE 061	08 CONG DIST 02
09 COORDINATES LATITUDE 39° 07' 12.8" LONGITUDE 84° 47' 39.2"		10 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER <input type="checkbox"/> G. UNKNOWN			

III. INSPECTION INFORMATION

01 DATE OF INSPECTION 10/10/90 MONTH DAY YEAR	02 SITE STATUS <input checked="" type="checkbox"/> ACTIVE <input type="checkbox"/> INACTIVE	03 YEARS OF OPERATION 1954 presently active BEGINNING YEAR ENDING YEAR	
04 AGENCY PERFORMING INSPECTION (Check all that apply) <input type="checkbox"/> A. EPA <input checked="" type="checkbox"/> B. EPA CONTRACTOR Ecology & Environment Inc. (Name of firm) <input type="checkbox"/> C. MUNICIPAL <input type="checkbox"/> D. MUNICIPAL CONTRACTOR (Name of firm) <input type="checkbox"/> E. STATE <input type="checkbox"/> F. STATE CONTRACTOR (Name of firm) <input type="checkbox"/> G. OTHER (Specify)			
05 CHIEF INSPECTOR Dennis Palmer	06 TITLE Chemist	07 ORGANIZATION Ecology and Environment Inc.	08 TELEPHONE NO. (312) 663-9415
09 OTHER INSPECTORS Russ Crittenden	10 TITLE Geographer	11 ORGANIZATION Same	12 TELEPHONE NO. () Same
Tim Mayers	Geographer	Same	() Same
Deborah Hallock	Biologist	Same	() Same
Jackie Vogt	Community Health Specialist	Same	() Same
			()
13 SITE REPRESENTATIVES INTERVIEWED Ralph Baxter	14 TITLE Operations Supervisor	15 ADDRESS 11001 Brower Road North Bend, OH 45052	16 TELEPHONE NO. (513) 941-4400
L.D. Turley	Refinery Manager	Same	() Same
Don Kittle	Maintenance Supervisor	Same	() Same
Dan Hemker	Project Engineer Superfund Site Management	575 Market Street San Francisco, CA 94120-7924	(415) 894-6915
			()
			()
17 ACCESS GAINED BY (Check one) <input checked="" type="checkbox"/> PERMISSION <input type="checkbox"/> WARRANT	18 TIME OF INSPECTION 0830-1730	19 WEATHER CONDITIONS rainy windy 40-50°F	
IV. INFORMATION AVAILABLE FROM			
01 CONTACT Mark A. Lehar	02 OF (Agency/Organization) Ohio EPA, Southwest District Office		03 TELEPHONE NO. (513) 285-6057
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM Scott A Turek	05 AGENCY U.S. EPA	06 ORGANIZATION Ecology and Environment, Inc.	07 TELEPHONE NO. (312) 663-9415
			08 DATE 7.16.91 MONTH DAY YEAR

[illegible]

EPA FORM 2070-13(7-81)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
04 D083364679

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☒ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 1,291 04 NARRATIVE DESCRIPTION

Refer to Section 2-3 and 5-2

01 ☒ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: unknown 04 NARRATIVE DESCRIPTION

Refer to Section 5-3

01 ☐ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

Refer to Section 5-4

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: NA 04 NARRATIVE DESCRIPTION

Refer to Section 5-5

01 ☒ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 70 04 NARRATIVE DESCRIPTION

Refer to Section 5-6

01 ☒ F. CONTAMINATION OF SOIL 02 ☒ OBSERVED (DATE: 10/10/90) ☐ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: 95 04 NARRATIVE DESCRIPTION
(Acres)

Refer to Table 4-1

01 ☒ G. DRINKING WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☒ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 1,291 04 NARRATIVE DESCRIPTION

Refer to Section 2-3

01 ☒ H. WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED: 30 04 NARRATIVE DESCRIPTION

Active facility

01 ☒ I. POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 1,291 04 NARRATIVE DESCRIPTION

Refer to A, B, E, G, and H above
Also refer to Section 5-6



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

OH D083364679

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☒ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☒ OBSERVED (DATE: 10/10/90)

☐ POTENTIAL

☐ ALLEGED

An area of distressed vegetation was observed between the six large storage tanks and the western part of the berm in the westernmost parcel of the southern section.

01 ☒ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION (include name(s) of species)

02 ☐ OBSERVED (DATE:)

☒ POTENTIAL

☐ ALLEGED

Fauna could be affected through the consumption of contaminated flora.

01 ☒ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE:)

☒ POTENTIAL

☐ ALLEGED

The food chain could be indirectly affected through the bioaccumulation of TCL compounds and TAL analytes.

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES
(Spills, Runoff, Standing liquids, Leaking drums)

02 ☐ OBSERVED (DATE:)

☐ POTENTIAL

☒ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: 1,291

04 NARRATIVE DESCRIPTION

spills of asphalt, gasoline, and #2 heating oil occurred from 1980-1983
See Section 2-3

01 ☒ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE:)

☒ POTENTIAL

☐ ALLEGED

potential for TCL compounds and TAL analytes to migrate to surface water

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE:)

☐ POTENTIAL

☐ ALLEGED

NA

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE:)

☐ POTENTIAL

☐ ALLEGED

NA

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

none known

III. TOTAL POPULATION POTENTIALLY AFFECTED: 1,291

IV. COMMENTS

Mercury was detected in a surface soil and a sediment from Dark Hollow Creek.
The ammonia/nitrate plume that was detected in groundwater during the 1970's was believed to originate off-site.

V. SOURCES OF INFORMATION (Cite specific references, e. g., state files, sample analysis, reports)

FIT file information
FIT SSI 10/10/90



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
OH 0083364679

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input checked="" type="checkbox"/> A. NPDES				outfall to Dark Hollow Creek
<input type="checkbox"/> B. UIC				
<input checked="" type="checkbox"/> C. AIR				
<input type="checkbox"/> D. RCRA				
<input type="checkbox"/> E. RCRA INTERIM STATUS				
<input checked="" type="checkbox"/> F. SPCC PLAN				
<input checked="" type="checkbox"/> G. STATE (Specify)				boiler
<input type="checkbox"/> H. LOCAL (Specify)				
<input type="checkbox"/> I. OTHER (Specify)				
<input type="checkbox"/> J. NONE				

III. SITE DESCRIPTION

01 STORAGE/ DISPOSAL (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT (Check all that apply)	05 OTHER
<input checked="" type="checkbox"/> A. SURFACE IMPOUNDMENT	unknown		<input type="checkbox"/> A. INCINERATION	<input checked="" type="checkbox"/> A. BUILDINGS ON SITE
<input type="checkbox"/> B. PILES			<input type="checkbox"/> B. UNDERGROUND INJECTION	
<input type="checkbox"/> C. DRUMS, ABOVE GROUND			<input type="checkbox"/> C. CHEMICAL/PHYSICAL	
<input checked="" type="checkbox"/> D. TANK, ABOVE GROUND			<input type="checkbox"/> D. BIOLOGICAL	12
<input type="checkbox"/> E. TANK, BELOW GROUND			<input type="checkbox"/> E. WASTE OIL PROCESSING	
<input type="checkbox"/> F. LANDFILL			<input type="checkbox"/> F. SOLVENT RECOVERY	06 AREA OF SITE
<input checked="" type="checkbox"/> G. LANDFARM	unknown		<input checked="" type="checkbox"/> G. OTHER RECYCLING/RECOVERY	95 (Acres)
<input type="checkbox"/> H. OPEN DUMP			<input type="checkbox"/> H. OTHER (Specify)	
<input type="checkbox"/> I. OTHER (Specify)				

07 COMMENTS

The surface impoundment is the lagoon located in the northern section.
The 1.2 million barrels is the storage tank capacity at the site.
Most of the waste is off-specification material which is normally recycled.

IV. CONTAINMENT

01 CONTAINMENT OF WASTES (Check one)
<input type="checkbox"/> A. ADEQUATE, SECURE <input type="checkbox"/> B. MODERATE <input checked="" type="checkbox"/> C. INADEQUATE, POOR <input type="checkbox"/> D. INSECURE, UNSOUND, DANGEROUS
02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC.
no liner exists for the lagoon Berms, diking, and other barriers exist to assure containment of tank leaks.

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE: <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
02 COMMENTS
Areas where TCL compounds and TAL analytes were detected in the soils are not readily accessible due to the Dark Hollow Creek, the berm system, fencing, and security.

VI. SOURCES OF INFORMATION (Cite specific references, e.g. state files, sample analysis, reports)

FIT file information
FIT SSI 10/10/90



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
04 D083364679

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY
(Check as applicable)

SURFACE WELL
COMMUNITY A. ☐ B. ☐
NON-COMMUNITY C. ☐ D. ☒

02 STATUS

ENDANGERED AFFECTED MONITORED
A. ☐ B. ☐ C. ☐
D. ☐ E. ☐ unknown F. ☐

03 DISTANCE TO SITE

A. > 3 (mi)
B. ~.8 (mi)

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (Check one)

☒ A. ONLY SOURCE FOR DRINKING ☐ B. DRINKING
(Other sources available)
COMMERCIAL, INDUSTRIAL, IRRIGATION
(No other water sources available)
☐ C. COMMERCIAL, INDUSTRIAL, IRRIGATION
(Limited other sources available)
☐ D. NOT USED, UNUSEABLE

02 POPULATION SERVED BY GROUND WATER 1,291

03 DISTANCE TO NEAREST DRINKING WATER WELL .8 (mi)

04 DEPTH TO GROUNDWATER

42.5 (ft)

05 DIRECTION OF GROUNDWATER FLOW

southwest

06 DEPTH TO AQUIFER
OF CONCERN

42.5 (ft)

07 POTENTIAL YIELD
OF AQUIFER

1,000 gpm (gpd)

08 SOLE SOURCE AQUIFER

☒ YES ☐ NO

09 DESCRIPTION OF WELLS (Including usage, depth, and location relative to population and buildings)

Refer to Section 5-2 of SSIR

10 RECHARGE AREA

☒ YES ☐ NO
COMMENTS

precipitation percolating
down to aquifer

11 DISCHARGE AREA

☒ YES ☐ NO
COMMENTS

Ohio River acts as
a discharge area

IV. SURFACE WATER

01 SURFACE WATER USE (Check one)

☒ A. RESERVOIR/RECREATION
DRINKING WATER SOURCE ☐ B. IRRIGATION, ECONOMICALLY
IMPORTANT RESOURCES ☐ C. COMMERCIAL, INDUSTRIAL ☐ D. NOT CURRENTLY USED

02 AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER

NAME:

Ohio River
Dark Hollow Creek
Little Creek

AFFECTED

DISTANCE TO SITE

☐ adjacent (mi)
☒ on-site (mi)
☐ (mi)

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN

ONE (1) MILE OF SITE
A. ~70
NO. OF PERSONS

TWO (2) MILES OF SITE
B. ~265
NO. OF PERSONS

THREE (3) MILES OF SITE
C. ~1600
NO. OF PERSONS

02 DISTANCE TO NEAREST POPULATION

.8 (mi)

03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE

~142

04 DISTANCE TO NEAREST OFF-SITE BUILDING

~50 ft (ft)

05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site, e.g., rural, village, densely populated urban area)

Refer to Section 2-2



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
OH D083364679

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (Check one)

☐ A. $10^{-6} - 10^{-8}$ cm/sec ☒ B. $10^{-4} - 10^{-6}$ cm/sec ☐ C. $10^{-4} - 10^{-3}$ cm/sec ☐ D. GREATER THAN 10^{-3} cm/sec

02 PERMEABILITY OF BEDROCK (Check one)

☐ A. IMPERMEABLE (Less than 10^{-8} cm/sec) ☒ B. RELATIVELY IMPERMEABLE ($10^{-4} - 10^{-6}$ cm/sec) ☐ C. RELATIVELY PERMEABLE ($10^{-2} - 10^{-4}$ cm/sec) ☐ D. VERY PERMEABLE (Greater than 10^{-2} cm/sec)

03 DEPTH TO BEDROCK

~81 (ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

unknown (ft)

05 SOIL pH

unknown

06 NET PRECIPITATION

6 (in)

07 ONE YEAR 24 HOUR RAINFALL

2.43 (in)

08 SLOPE

SITE SLOPE

<1 %

DIRECTION OF SITE SLOPE

South

TERRAIN AVERAGE SLOPE

<1 %

09 FLOOD POTENTIAL

SITE IS IN 100 YEAR FLOODPLAIN

10

NA

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

ESTUARINE

A. NA (mi)

OTHER

B. NA (mi)

12 DISTANCE TO CRITICAL HABITAT (of endangered species)

NA (mi)

ENDANGERED SPECIES: NA

13 LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL INDUSTRIAL

RESIDENTIAL AREAS; NATIONAL STATE PARKS
FORESTS, OR WILDLIFE RESERVES

AGRICULTURAL LANDS
PRIME AG LAND AG LAND

A. adjacent (mi)

B. 3 (mi)

C. NA (mi) D. NA (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

Adjacent to Ohio River
See Appendix A

VII. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

FIT file information
U.S. Department of Commerce, 1979, Climatic Atlas of the U.S. Climatic Center, Asheville, NC
USGS Lawrenceburg KY Quadrangle, 1961, 1:24,000.



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
OH D083364679

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER	1 production well	NET Midwest Inc. Bartlett, IL - TCL Southwest Labs of Oklahoma, Broken Arrow, OK - TAL	now available
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
SPILL			
SOIL	10 soil/ sediment samples	NET Midwest Inc. Bartlett, IL - TCL Southwest Labs of Oklahoma, Broken Arrow, OK - TAL	now available
VEGETATION			
OTHER			

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS
OVA 128 Combination oxygen and explosimeter	up to 10ppm in basin area of lagoon no readings above background
Rad-mini Drager pump with HCN tubes	no readings above background no color change

IV. PHOTOGRAPHS AND MAPS

01 TYPE <input checked="" type="checkbox"/> GROUND <input type="checkbox"/> AERIAL	02 IN CUSTODY OF Ecology & Environment Inc., Chicago, IL <small>(Name of organization or individual)</small>
03 MAPS <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS Ecology and Environment Inc., Chicago, IL

V. OTHER FIELD DATA COLLECTED (Provide narrative description)

Ph, conductivity, and temperature of
groundwater sample
(refer to Table 4-2)

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

FIT SSI 10/10/90
FIT file information



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 7 - OWNER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
OH D083364679

II. CURRENT OWNER(S)				PARENT COMPANY (if applicable)			
01 NAME Chevron USA Inc.		02 D+B NUMBER unknown		08 NAME Chevron Corporation		09 D+B NUMBER unknown	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 11001 Brower Rd		04 SIC CODE unknown		10 STREET ADDRESS (P.O. Box, RFD #, etc.) 575 Market Street		11 SIC CODE unknown	
05 CITY North Bend		06 STATE OH	07 ZIP CODE 45052	12 CITY San Francisco		13 STATE CA	14 ZIP CODE 94120-7924
01 NAME		02 D+B NUMBER		08 NAME NA		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME NA		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME NA		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
III. PREVIOUS OWNER(S) (List most recent first)				IV. REALTY OWNER(S) (if applicable; list most recent first)			
01 NAME Standard Oil Company of California		02 D+B NUMBER unknown		01 NAME NA		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) unknown		04 SIC CODE unknown		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY unknown		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
01 NAME NA		02 D+B NUMBER		01 NAME NA		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
01 NAME NA		02 D+B NUMBER		01 NAME NA		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)							
FIT SSI 10/10/90							



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

OH D083364679

II. CURRENT OPERATOR (Provide if different from owner)

OPERATOR'S PARENT COMPANY (if applicable)

01 NAME <i>Chevron USA Inc.</i>		02 D+B NUMBER <i>unknown</i>		10 NAME <i>Chevron Corporation</i>		11 D+B NUMBER <i>unknown</i>	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) <i>11001 Brower Road</i>		04 SIC CODE <i>unknown</i>		12 STREET ADDRESS (P.O. Box, RFD #, etc.) <i>575 Market Street</i>		13 SIC CODE <i>unknown</i>	
05 CITY <i>North Bend</i>		06 STATE <i>OH</i>	07 ZIP CODE <i>45052</i>	14 CITY <i>San Francisco</i>		15 STATE <i>CA</i>	16 ZIP CODE <i>94120-7924</i>
08 YEARS OF OPERATION <i>1954 - present</i>		09 NAME OF OWNER <i>Chevron USA Inc.</i>					

III. PREVIOUS OPERATOR(S) (List most recent first; provide only if different from owner)

PREVIOUS OPERATORS' PARENT COMPANIES (if applicable)

01 NAME <i>unknown</i>		02 D+B NUMBER		10 NAME <i>unknown</i>		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME <i>unknown</i>		02 D+B NUMBER		10 NAME <i>unknown</i>		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME <i>unknown</i>		02 D+B NUMBER		10 NAME <i>unknown</i>		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

IV. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

FIT SSI 10/10/90



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
OH D083364679

II. ON-SITE GENERATOR

01 NAME Chevron USA Inc Cincinnati Asphalt Refinery	02 D+B NUMBER unknown		
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 11001 Brower Road	04 SIC CODE unknown		
05 CITY North Bend	06 STATE OH	07 ZIP CODE 45052	

III. OFF-SITE GENERATOR(S)

01 NAME receives finished liquid asphalt from refinery	02 D+B NUMBER unknown	01 NAME NA	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.) unknown	04 SIC CODE unknown	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY near Pascagoula	06 STATE Miss	07 ZIP CODE	
01 NAME NA	02 D+B NUMBER	01 NAME NA	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE	07 ZIP CODE	

IV. TRANSPORTER(S)

01 NAME Rumke	02 D+B NUMBER unknown	01 NAME NA	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.) unknown	04 SIC CODE unknown	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY Cincinnati	06 STATE OH	07 ZIP CODE	
01 NAME NA	02 D+B NUMBER	01 NAME NA	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE	07 ZIP CODE	

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

FIT SSI 10/10/90
FIT file information



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

L IDENTIFICATION

01 STATE 02 SITE NUMBER

OH 0083364679

II. PAST RESPONSE ACTIVITIES

01 ☐ A. WATER SUPPLY CLOSED
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ B. TEMPORARY WATER SUPPLY PROVIDED
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ C. PERMANENT WATER SUPPLY PROVIDED
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ D. SPILLED MATERIAL REMOVED
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ E. CONTAMINATED SOIL REMOVED
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ F. WASTE REPACKAGED
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ G. WASTE DISPOSED ELSEWHERE
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ H. ON SITE BURIAL
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ I. IN SITU CHEMICAL TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ J. IN SITU BIOLOGICAL TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ K. IN SITU PHYSICAL TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ L. ENCAPSULATION
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ M. EMERGENCY WASTE TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ N. CUTOFF WALLS
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ O. EMERGENCY DIKING/SURFACE WATER DIVERSION
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ P. CUTOFF TRENCHES/SUMP
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ Q. SUBSURFACE CUTOFF WALL
04 DESCRIPTION

02 DATE

03 AGENCY

NA



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
OH D083364679

II PAST RESPONSE ACTIVITIES (Continued)

01 ☐ R. BARRIER WALLS CONSTRUCTED
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ S. CAPPING/COVERING
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ T. BULK TANKAGE REPAIRED
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ U. GROUT CURTAIN CONSTRUCTED
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ V. BOTTOM SEALED
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ W. GAS CONTROL
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ X. FIRE CONTROL
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ Y. LEACHATE TREATMENT
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ Z. AREA EVACUATED
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ 1. ACCESS TO SITE RESTRICTED
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ 2. POPULATION RELOCATED
04 DESCRIPTION

02 DATE

03 AGENCY

NA

01 ☐ 3. OTHER REMEDIAL ACTIVITIES
04 DESCRIPTION

02 DATE

03 AGENCY

NA

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

FIT file information
FIT SSI 10/10/90



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 11 - ENFORCEMENT INFORMATION

I. IDENTIFICATION

01 STATE	02 SITE NUMBER
OH	D 083364679

II. ENFORCEMENT INFORMATION

01 PAST REGULATORY/ENFORCEMENT ACTION ☐ YES ☒ NO

02 DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

Refer to Section 2-3

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

refer to references

APPENDIX C

FIT SITE PHOTOGRAPHS

FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chevron USA Inc - Cincinnati Asphalt Refinery

PAGE 1 OF 20

U.S. EPA ID: OH D 083 364 679 TDD: F05-8804-005

PAN: FOH 05565BR

DATE: 10/10/90

TIME: 1300

DIRECTION OF
PHOTOGRAPH:

West

WEATHER

CONDITIONS:

Rain, 60-70°F


PHOTOGRAPHED BY:

D. Palmer

SAMPLE ID

(if applicable):

S1



DESCRIPTION: Photo placard of Sediment Sample S1 (placard was
mistakenly labelled as S2).

DATE: 10/10/90

TIME: 1300

DIRECTION OF
PHOTOGRAPH:

West

WEATHER

CONDITIONS:

Rain, 60-70°F

PHOTOGRAPHED BY:

D. Palmer

SAMPLE ID

(if applicable):

S1



DESCRIPTION: Perspective photograph of Sediment Sample S1 sample
point and placard.

FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chevron USA Inc - Cincinnati Asphalt Refinery PAGE 2 OF 20

U.S. EPA ID: OH D 083 364679 TDD: F05-8804-005

PAN: FOH05565BR

DATE: 10/10/90

TIME: 1300

DIRECTION OF
PHOTOGRAPH: SW

WEATHER
CONDITIONS: Rain, 60-70°F

PHOTOGRAPHED BY: D. Palmer

SAMPLE ID
(if applicable): S1

DESCRIPTION: View from near
Sediment Sample Point S1
of the east branch of
Dark Hollow Creek
flowing toward Chevron
Site.



FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chevron USA Inc - Cincinnati Asphalt Refinery

PAGE 3 OF 20

U.S. EPA ID: OH D 083 364 679 TDD: F05-8804-005

PAN: FOH 05565BR

DATE: 10/10/98

TIME: 1200

DIRECTION OF
PHOTOGRAPH:

Southwest

WEATHER

CONDITIONS:

Rain, 60-70°F

PHOTOGRAPHED BY:


D. Palmer

SAMPLE ID

(if applicable):

S2

DESCRIPTION: Photograph of Sediment Sample S2 sample point
and placard.



DATE: 10/10/98

TIME: 1200

DIRECTION OF
PHOTOGRAPH:

South west

WEATHER

CONDITIONS:

Rain, 60-70°F

PHOTOGRAPHED BY:

D. Palmer

SAMPLE ID

(if applicable):

DESCRIPTION: Perspective photograph of Sediment Sample S2 sample
point on Dark Hollow Creek.



FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chevron USA Inc - Cincinnati Asphalt Refinery

PAGE 4 OF 20

U.S. EPA ID: OHD 083 364 679 TDD: F05-8804-005

PAN: FOH 05565BR

DATE: 10/10/90

TIME: 1300

DIRECTION OF
PHOTOGRAPH:

Southeast

WEATHER
CONDITIONS:


Rain, 60-70°F

PHOTOGRAPHED BY:

T. Mayer

SAMPLE ID
(if applicable):

S3



DESCRIPTION: Photograph of Sediment Sample Point S3 and placard.

DATE: 10/10/90

TIME: 1300

DIRECTION OF
PHOTOGRAPH:

Southeast

WEATHER
CONDITIONS:

Rain, 60-70°F

PHOTOGRAPHED BY:

T. Mayer

SAMPLE ID
(if applicable):

S3



DESCRIPTION: Perspective of Sediment Sample Point S3 and placard.

FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chertron USA Inc - Cincinnati Asphalt Refinery

PAGE 5 OF 20

U.S. EPA ID: OH D 083 364 679 TDD: F05-8804-005

PAN: FOH 05565BR

DATE: 10/10/98

TIME: 1315

DIRECTION OF
PHOTOGRAPH:

Southeast

WEATHER
CONDITIONS:


Rain, 60-70°F

PHOTOGRAPHED BY:

T. Mayers

SAMPLE ID
(if applicable):

S4



DESCRIPTION: Photograph of Soil Sample Point S4 and placard.

DATE: 10/10/98

TIME: 1315

DIRECTION OF
PHOTOGRAPH:

East

WEATHER
CONDITIONS:

Rain, 60-70°F

PHOTOGRAPHED BY:

T. Mayers

SAMPLE ID
(if applicable):

S4



DESCRIPTION: Perspective photograph of Soil Sample Point S4 and placard.

FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Cherwon USA Inc - Cincinnati Asphalt Refinery

PAGE 6 OF 20

U.S. EPA ID: OH D 083 364 679 TDD: F05-8804-005

PAN: FOH 05565BR

DATE: 10/18/98

TIME: 1415

DIRECTION OF
PHOTOGRAPH:

South

WEATHER
CONDITIONS:

Rain, 60-70°F

PHOTOGRAPHED BY:

T. Mayers

SAMPLE ID
(if applicable):

S5



DESCRIPTION: Photograph of Sediment Sample S5 point and placard
at Dark Hollow Creek

DATE: 10/18/98

TIME: 1415

DIRECTION OF
PHOTOGRAPH:

South

WEATHER
CONDITIONS:

Rain, 60-70°F

PHOTOGRAPHED BY:

T. Mayers

SAMPLE ID
(if applicable):

S5



DESCRIPTION: Photograph of location of Sediment Sample S5 point
on Dark Hollow Creek. Sample point was on left of photograph
near foreground.

FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chercon USA Inc - Cincinnati Asphalt Refinery

PAGE 7 OF 20

U.S. EPA ID: OHD 083 364 679 TDD: F05-8804-005

PAN: FOH 05565BR

DATE: 10/11/90

TIME: 830

DIRECTION OF
PHOTOGRAPH:

South

WEATHER
CONDITIONS:

Sunny, 70°F

PHOTOGRAPHED BY:

D. Palmer

SAMPLE ID
(if applicable):

85



DESCRIPTION: Perspective photo of Sediment Sample Point 85 location.
Inclusion of guard rail was to more accurately establish 85 location

DATE: 10/11/90

TIME: 830

DIRECTION OF
PHOTOGRAPH:

East

WEATHER
CONDITIONS:


Sunny, 70°F

PHOTOGRAPHED BY:

D. Palmer

SAMPLE ID
(if applicable):

85



DESCRIPTION: View to the east from same point as the upper
photograph taken.

FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chercon USA Inc - Cincinnati Asphalt Refinery

PAGE 8 OF 20

U.S. EPA ID: OHD 083 364 679 TDD: F05-8804-005

PAN: FOH 05565BR

DATE: 10/18/98

TIME: 1400

DIRECTION OF
PHOTOGRAPH:

South east

WEATHER

CONDITIONS:

Rain, 60-70°F

PHOTOGRAPHED BY:

T. Mayers

SAMPLE ID

(if applicable):

S6



DESCRIPTION: Photograph of Soil Sample Point S6 and placard.

DATE: 10/18/98

TIME: 1400

DIRECTION OF
PHOTOGRAPH:

North

WEATHER

CONDITIONS:

Rain, 60-70°F

PHOTOGRAPHED BY:

T. Mayers

SAMPLE ID

(if applicable):

S6



DESCRIPTION: Perspective photograph of Soil Sample Point S6 and placard.

FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chevron USA Inc - Cincinnati Asphalt Refinery

PAGE 9 OF 20

U.S. EPA ID: OH D 083 364 679 TDD: F05-8804-005

PAN: F0405565BR

DATE: 10/11/90

TIME: 840

DIRECTION OF
PHOTOGRAPH:

West

WEATHER
CONDITIONS:

Sunny, 70°F

PHOTOGRAPHED BY:

D. Palmer

SAMPLE ID
(if applicable):

S6



DESCRIPTION: Perspective of Soil Sample Point S6 location
from the berm.

FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chevron USA Inc - Cincinnati Asphalt Refinery

PAGE 1 of 2

U.S. EPA ID: OHD 083 364 679 TDD: F05-8804-005

PAN: F014 0556 SBR

DATE: 10/10/90

TIME: 1400

DIRECTION OF
PHOTOGRAPH:

West

WEATHER

CONDITIONS:

Rain, 60-70°F

PHOTOGRAPHED BY:

D. Palmer

SAMPLE ID

(if applicable):

S7

DESCRIPTION: Photograph of Soil Sample Point S7 and placard



DATE: 10/10/90

TIME: 1400

DIRECTION OF

PHOTOGRAPH: W

WEATHER

CONDITIONS: Rain, 60-70°F

PHOTOGRAPHED BY: D. Palmer

SAMPLE ID

(if applicable): S7

DESCRIPTION: Perspective

photo graph of location

of Soil Sample Point S7

and placard



FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chevron USA Inc - Cincinnati Asphalt Refinery

PAGE 11 OF 20

U.S. EPA ID: OHD 083 364 679 TDD: F05-8804-005

PAN: F014 0556 SBR

DATE: 10/10/90

TIME: 1430

DIRECTION OF
PHOTOGRAPH:

South

WEATHER
CONDITIONS:

Rain, 60-70°F

PHOTOGRAPHED BY:

D. Palmer

SAMPLE ID
(if applicable):

S8



DESCRIPTION: Photograph of Soil Sample Point S8 and placard.

DATE: 10/10/90

TIME: 1430

DIRECTION OF
PHOTOGRAPH:

S

WEATHER

CONDITIONS: Rain, 60-70°F

PHOTOGRAPHED BY: D. Palmer

SAMPLE ID
(if applicable): S8

DESCRIPTION: Perspective

Photograph of Soil Sample
Point S8 location and
placard.



FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chevron USA Inc - Cincinnati Asphalt Refinery PAGE 12 OF 20

U.S. EPA ID: OHD 083 364 679 TDD: F05-8804-005 PAN: FOH 0556SBR

DATE: 10/10/90

TIME: 1530

DIRECTION OF
PHOTOGRAPH:

South east

WEATHER
CONDITIONS:


Rain, 60-70°F

PHOTOGRAPHED BY:

T. Mayers

SAMPLE ID
(if applicable):

S9



DESCRIPTION: Photograph of Soil Sample Point S9 and placard.

DATE: 10/10/90

TIME: 1530

DIRECTION OF
PHOTOGRAPH:

South east

WEATHER
CONDITIONS:

Rain, 60-70°F

PHOTOGRAPHED BY:

T. Mayers

SAMPLE ID
(if applicable):

S9



DESCRIPTION: Perspective photograph of Soil Sample Point S9 location and placard.

FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chertron USA Inc - Cincinnati Asphalt Refinery

PAGE 13 OF 20

U.S. EPA ID: OH D 083 364 679 TDD: F05-8804-005

PAN: FOH 05565BR

DATE: 10/10/98

TIME: 1500

DIRECTION OF
PHOTOGRAPH:

North

WEATHER
CONDITIONS:

Rain, 60-70°F

PHOTOGRAPHED BY:

T. Mayers

SAMPLE ID
(if applicable):

S10



DESCRIPTION: Photograph of Soil Sample Point S10 and placard.

DATE: 10/10/98

TIME: 1500

DIRECTION OF
PHOTOGRAPH:

North

WEATHER
CONDITIONS:

Rain, 60-70°F

PHOTOGRAPHED BY:

T. Mayers

SAMPLE ID
(if applicable):

S10



DESCRIPTION: Perspective photograph of Soil Sample Point S10 location and placard.

FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chevron USA Inc-Cincinnati Asphalt Refinery PAGE 14 OF 20

U.S. EPA ID: OH D 083 364679 TDD: F05-8804-005

PAN: FOH05565BR

DATE: 10/11/98

TIME: 900

DIRECTION OF
PHOTOGRAPH: E

WEATHER
CONDITIONS: Sunny, 70°F

PHOTOGRAPHED BY: D. Palmer

SAMPLE ID
(if applicable): S10

DESCRIPTION: Perspective

photograph of Soil Sample

Point S10 location.



FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chevron USA Inc - Cincinnati Asphalt Refinery PAGE 15 OF 20

U.S. EPA ID: OH D 083 364679 TDD: F05-8804-005

PAN: F0H05565BR

DATE: 10/10/90

TIME: 1530

DIRECTION OF
PHOTOGRAPH: S

WEATHER
CONDITIONS: Rain, 60-70°F

PHOTOGRAPHED BY: D. Palmer

SAMPLE ID
(if applicable): PW1

DESCRIPTION: Photograph of
Production Well Sample
Point PW1. The Well
is identified as P337,
the South Well



FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chevron USA Inc - Cincinnati Asphalt Refinery PAGE 16 OF 20

U.S. EPA ID: OH 083 364679 TDD: F05-8804-005

PAN: FOH05565BR

DATE: 10/10/90

TIME: 1530


DIRECTION OF
PHOTOGRAPH: S

WEATHER
CONDITIONS: Rain, 60-70°F

PHOTOGRAPHED BY: D. Palmer

SAMPLE ID
(if applicable): PW1

DESCRIPTION: Perspective
photograph of Production
Well Sample Point PW 1.



FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chertron USA Inc - Cincinnati Asphalt Refinery

PAGE 17 OF 20

U.S. EPA ID: OH D 083 364 679 TDD: F05-8804-005

PAN: FOH 05565BR

DATE: 10/11/90

TIME: 815

DIRECTION OF
PHOTOGRAPH:

East

WEATHER
CONDITIONS:

Sunny, 70°F

PHOTOGRAPHED BY:

D. Palmer

SAMPLE ID
(if applicable):

N/A

DESCRIPTION: Photograph of Outfall 001.



DATE: 10/11/90

TIME: 810

DIRECTION OF
PHOTOGRAPH:

East

WEATHER
CONDITIONS:

Sunny, 70°F

PHOTOGRAPHED BY:

D. Palmer

SAMPLE ID
(if applicable):

N/A

DESCRIPTION: Photograph of Unit (a.k.a. Tank) 304. A lagoon is beside and below the level of the tank. It is located to the right of the Tank 304 in the photograph.



FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chevron USA Inc - Cincinnati Asphalt Refinery

PAGE 18 OF 28

U.S. EPA ID: OH D 83 364 679

TDD: F85-8884-885

PAN: FOH 8556 SBR



DATE: 10/11/98 TIME: 818 DIRECTION OF PHOTOGRAPH: N PHOTOGRAPHED BY: D. Palmer

WEATHER CONDITIONS: Sunny, 78°F SAMPLE ID (if applicable): _____

DESCRIPTION: Panoramic photographs of the lagoon beside Tank 384.

FIELD PHOTOGRAPHY LOG SHEET


SITE NAME: Cherron USA Inc. — Cincinnati Asphalt Refinery

PAGE 19 OF 20

U.S. EPA ID: OHD 083 364 679

TDD: F05-8804-005

PAN: FOH0556SBR



DATE: 10/11/94 TIME: 845 DIRECTION OF PHOTOGRAPH: South PHOTOGRAPHED BY: D. Palmer

WEATHER CONDITIONS: Sunny, 78°F SAMPLE ID (if applicable): N/A

DESCRIPTION: Panoramic photography of barge loading terminal on the Ohio River.

FIELD PHOTOGRAPHY LOG SHEET

SITE NAME: Chevron USA Inc - Cincinnati Asphalt Refinery

PAGE 20 OF 20

U.S. EPA ID: OHD 083 364 679 TDD: F05-8804-005

PAN: F014 0556 SBR

DATE: 10/11/90

TIME: 905

DIRECTION OF
PHOTOGRAPH:

North

WEATHER

CONDITIONS:

Sunny, 70°F


PHOTOGRAPHED BY:

D. Palmer

SAMPLE ID

(if applicable):

N/A



DESCRIPTION: Photograph showing location of boiler-house. It is the structure with the corrugated metal roof.

DATE: 10/11/90

TIME: 905

DIRECTION OF
PHOTOGRAPH:

NE

WEATHER

CONDITIONS:

Sunny, 70°F

PHOTOGRAPHED BY:

D. Palmer

SAMPLE ID

(if applicable):

N/A

DESCRIPTION: Photograph of the furnaces on-site. Their function is to supply hot water and steam for operational purposes.



APPENDIX D

U.S. EPA TARGET COMPOUND LIST AND
TARGET ANALYTE LIST
QUANTITATION/DETECTION LIMITS

ROUTINE ANALYTICAL SERVICES
CONTRACT REQUIRED DETECTION AND QUANTITATION LIMITS

Contract Laboratory Program
Target Compound List
Quantitation Limits

COMPOUND	CAS #	WATER	SOIL SEDIMENT SLUDGE
Chloromethane	74-87-3	10 ug/L	10 ug/Kg
Bromomethane	74-83-9	10	10
Vinyl chloride	75-01-4	10	10
Chloroethane	75-00-3	10	10
Methylene chloride	75-09-2	5	5
Acetone	67-64-1	10	5
Carbon disulfide	75-15-0	5	5
1,1-dichloroethene	75-35-4	5	5
1,1-dichloroethane	75-34-3	5	5
1,2-dichloroethene (total)	540-59-0	5	5
Chloroform	67-66-3	5	5
1,2-dichloroethane	107-06-2	5	5
2-butanone (MEK)	78-93-3	10	10
1,1,1-trichloroethane	71-55-6	5	5
Carbon tetrachloride	56-23-5	5	5
Vinyl acetate	108-05-4	10	10
Bromodichloromethane	75-27-4	5	5
1,2-dichloropropane	78-87-5	5	5
cis-1,3-dichloropropene	10061-01-5	5	5
Trichloroethene	79-01-6	5	5
Dibromochloromethane	124-48-1	5	5
1,1,2-trichloroethane	79-00-5	5	5
Benzene	71-43-2	5	5
Trans-1,3-dichloropropene	10061-02-6	5	5
Bromoform	75-25-2	5	5
4-Methyl-2-pentanone	108-10-1	10	10
2-Hexanone	591-78-6	10	10
Tetrachloroethene	127-18-4	5	5
Toluene	108-88-3	5	5
1,1,2,2-tetrachloroethane	79-34-5	5	5
Chlorobenzene	108-90-7	5	5
Ethyl benzene	100-41-4	5	5
Styrene	100-42-5	5	5
Xylenes (total)	1330-20-7	5	5

Table A
Contract Laboratory Program
Target Compound List
Semivolatiles Quantitation Limits

COMPOUND	CAS #	WATER	SOIL SEDIMENT SLUDGE
Phenol	108-95-2	10 ug/L	330 ug/Kg
bis(2-Chloroethyl) ether	111-44-4	10	330
2-Chlorophenol	95-57-8	10	330
1,3-Dichlorobenzene	541-73-1	10	330
1,4-Dichlorobenzene	106-46-7	10	330
Benzyl Alcohol	100-51-6	10	330
1,2-Dichlorobenzene	95-50-1	10	330
2-Methylphenol	95-48-7	10	330
bis(2-Chloroisopropyl) ether	108-60-1	10	330
4-Methylphenol	106-44-5	10	330
N-Nitroso-di-n-dipropylamine	621-64-7	10	330
Hexachloroethane	67-72-1	10	330
Nitrobenzene	98-95-3	10	330
Isophorone	78-59-1	10	330
2-Nitrophenol	88-75-5	10	330
2,4-Dimethylphenol	105-67-9	10	330
Benzoic Acid	65-85-0	50	1600
bis(2-Chloroethoxy) methane	111-91-1	10	330
2,4-Dichlorophenol	120-83-2	10	330
1,2,4-Trichlorobenzene	120-82-1	10	330
Naphthalene	91-20-3	10	330
4-Chloroaniline	106-47-8	10	330
Hexachlorobutadiene	87-68-3	10	300
4-Chloro-3-methylphenol	59-50-7	10	330
2-Methylnaphthalene	91-57-6	10	330
Hexachlorocyclopentadiene	77-47-4	10	330
2,4,6-Trichlorophenol	88-06-2	10	330
2,4,5-Trichlorophenol	95-95-4	50	1600
2-Chloronaphthalene	91-58-7	10	330
2-Nitroaniline	88-74-4	50	1600
Dimethylphthalate	131-11-3	10	330
Acenaphthylene	208-96-8	10	330
2,6-Dinitrotoluene	606-20-2	10	330
3-Nitroaniline	99-09-2	50	1600
Acenaphthene	83-32-9	10	330
2,4-Dinitrophenol	51-28-5	50	1600
4-Nitrophenol	100-02-7	50	1600
Dibenzofuran	132-64-9	10	330
2,4-Dinitrotoluene	121-14-2	10	330
Diethylphthalate	84-66-2	10	330
4-Chlorophenyl-phenyl ether	7005-72-3	10	330

Table A
Contract Laboratory Program
Target Compound List
Semivolatiles Quantitation Limits

COMPOUND	CAS #	WATER	SOIL SLUDGE SEDIMENT
Fluorene	86-73-7	10 ug/L	330 ug/Kg
4-Nitroaniline	100-01-6	50	1600
4,6-Dinitro-2-methylphenol	534-52-1	50	1600
N-nitrosodiphenylamine	86-30-6	10	330
4-Bromophenyl-phenylether	101-55-3	10	330
Hexachlorobenzene	118-74-1	10	330
Pentachlorophenol	87-86-5	50	1600
Phenanthrene	85-01-8	10	330
Anthracene	120-12-7	10	330
Di-n-butylphthalate	84-74-2	10	330
Fluoranthene	206-44-0	10	330
Pyrene	129-00-0	10	330
Butylbenzylphthalate	85-68-7	10	330
3,3'-Dichlorobenzidine	91-94-1	20	660
Benzo(a)anthracene	56-55-3	10	330
Chrysene	218-01-9	10	330
bis(2-Ethylhexyl)phthalate	117-81-7	10	330
Di-n-octylphthalate	117-84-0	10	330
Benzo(b)fluoranthene	205-99-2	10	330
Benzo(k)fluoranthene	207-08-9	10	330
Benzo(a)pyrene	50-32-8	10	330
Indeno(1,2,3-cd)pyrene	193-39-5	10	330
Dibenz(a,h)anthracene	53-70-3	10	330
Benzo(g,h,i)perylene	191-24-2	10	330

Table A
Contract Laboratory Program
Target Compound List
Pesticide and PCB Quantitation Limits

COMPOUND	CAS #	WATER	SOIL
			SEDIMENT SLUDGE
alpha-BHC	319-84-6	0.05 ug/L	8 ug/Kg
beta-BHC	319-85-7	0.05	8
delta-BHC	319-86-8	0.05	8
gamma-BHC (Lindane)	58-89-9	0.05	8
Heptachlor	76-44-8	0.05	8
Aldrin	309-00-2	0.05	8
Heptachlor epoxide	1024-57-3	0.05	8
Endosulfan I	959-98-8	0.05	8
Dieldrin	60-57-1	0.10	16
4,4'-DDE	72-55-9	0.10	16
Endrin	72-20-8	0.10	16
Endosulfan II	33213-65-9	0.10	16
4,4'-DDD	72-54-8	0.10	16
Endosulfan sulfate	1031-07-8	0.10	16
4,4'-DDT	50-29-3	0.10	16
Methoxychlor (Mariate)	72-43-5	0.5	80
Endrin ketone	53494-70-5	0.10	16
alpha-Chlordane	5103-71-9	0.5	80
gamma-chlordane	5103-74-2	0.5	80
Toxaphene	8001-35-2	1.0	160
AROCLOR-1016	12674-11-2	0.5	80
AROCLOR-1221	11104-28-2	0.5	80
AROCLOR-1232	11141-16-5	0.5	80
AROCLOR-1242	53469-21-9	0.5	80
AROCLOR-1248	12672-29-6	0.5	80
AROCLOR-1254	11097-69-1	1.0	160
AROCLOR-1260	11096-82-5	1.0	160

Table A (Cont.)

CONTRACT LABORATORY PROGRAM
 TARGET ANALYTE LIST (TAL)
 INORGANIC DETECTION LIMITS

Compound	Procedure	Detection Limits	
		Water (µg/L)	Soil Sediment Sludge (mg/kg)
aluminum	ICP	200	40
antimony	furnace	60	2.4
arsenic	furnace	10	2
barium	ICP	200	40
beryllium	ICP	5	1
cadmium	ICP	5	1
calcium	ICP	5,000	1,000
chromium	ICP	10	2
cobalt	ICP	50	10
copper	ICP	25	5
iron	ICP	100	20
lead	furnace	5	1
magnesium	ICP	5,000	1,000
manganese	ICP	15	3
mercury	cold vapor	0.2	0.008
nickel	ICP	40	8
potassium	ICP	5,000	1,000
selenium	furnace	5	1
silver	ICP	10	2
sodium	ICP	5,000	1,000
thallium	furnace	10	2
tin	ICP	40	8
vanadium	ICP	50	10
zinc	ICP	20	4
cyanide	color	10	2

3767:1

APPENDIX E

SOIL BORING LOGS OF THE AREA OF THE SITE

WELL LOG AND DRILLING REPORT
State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
1500 Dublin Road
Columbus, Ohio

SOIL BORING LOG 1

No. 179978

County Hamilton Township Miami Section of Township _____

Owner E. I. DuPont de Nemours & Co. Address Ft. Hill Plant, North Bend, Ohio

Location of property _____

CONSTRUCTION DETAILS

Casing diameter 5" Length of casing _____
Type of screen 1" Everdun Length of screen 6 ft.
Type of pump _____
Capacity of pump _____
Depth of pump setting _____
Date of completion _____

BAILING OR PUMPING TEST


Pumping rate _____ G.P.M. Duration of test _____ hrs.
Drawdown _____ ft. Date _____
Developed capacity _____
Static level—depth to water _____ ft.
Pump installed by _____

WELL LOG

Formations Sandstone, shale, limestone, gravel and clay	From	To
	0 Feet	_____ Ft.
<u>TEST HOLE #1</u>		
Top Soil	0'	5'
Yellow Clay	5'	10'
Clay, Some Gravel	10'	16'
Coarse Gravel & Boulders	16'	24'
Clay	24'	28'
Sand, Some Gravel	28'	39'
Clay	39'	40'
Fine Dirty Sand, Some Gravel	40'	50'
Dirty Sand	50'	75'
Good Coarse Gravel	75'	79'
Sand and Gravel	79'	85'
Coarse Sand & Gravel	85'	90'
Good Coarse Sand & Gravel	90'	97'
Coarse Gravel, Some Sand	97'	100'
Gravel and Boulders	100'	101'
Rock	101'	103'

SKETCH SHOWING LOCATION

Locate in reference to numbered
State Highways, St. Intersections, County roads, etc.



See reverse side for instructions

Drilling Firm Diehl Pump & Supply Co., Inc Date January 12, 1962

Address 2985 Race Road, Cinti. 11, Ohio

Signed _____

Edward B. Wagner
Diehl Pump & Supply Co. Inc.

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
1500 Dublin Road
Columbus, Ohio

SOIL BORING LOG 2

No. 179979

County Hamilton Township Miami Section of Township _____
Owner E. I. DuPont de Nemours & Co. Address Ft. Hill Plant, North Bend, Ohio
Location of property _____

CONSTRUCTION DETAILS

Casing diameter 5" Length of casing _____
Type of screen _____ Length of screen _____
Type of pump _____
Capacity of pump _____
Depth of pump setting _____
Date of completion 11-15-61

BAILING OR PUMPING TEST

Pumping rate _____ G.P.M. Duration of test _____ hrs.
Drawdown _____ ft. Date _____
Developed capacity _____
Static level—depth to water _____ ft.
Pump installed by _____

WELL LOG

SKETCH SHOWING LOCATION

Formations
Sandstone, shale, limestone,
gravel and clay

From

To

Locate in reference to numbered
State Highways, St. Intersections, County roads, etc.

TEST HOLE #2

0 Feet

_____ Ft.

N.

Soil & Clay
Yellow Clay
Clay
Coarse Dirty Gravel
Coarse Gravel
Clay
Sandy Clay & Gravel
Sand
Coarse Sand
Coarse Sand, Some Gravel
Coarse Sand
Good Coarse Sand & Gravel
Coarse Sand and Gravel
Good Coarse Gravel & Sand
Rock

0'	15'
15'	20'
20'	25'
25'	30'
30'	38'
38'	41'
41'	45'
45'	50'
50'	58'
58'	75'
75'	80'
80'	85'
85'	90'
90'	98 1/2'
98 1/2'	100 1/2'

W.

E.

Refer Log 179978

S.

See reverse side for instructions

Drilling Firm Diehl Pump & Supply Co.

Address 3985 Race Rd., Cinti. 11, Ohio

Date January 12, 1962

Signed

Edward B. Wagner 65
Diehl Pump & Supply Co. Inc.

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
1500 Dublin Road
Columbus, Ohio

SOIL BORING LOG 3

No. 179980

County Hamilton Township Miami Section of Township _____

Owner E. I. duPont Denemours & Co. Address Ft. Hill Plant, North Bend, Ohio

Location of property _____

CONSTRUCTION DETAILS	BAILING OR PUMPING TEST
Casing diameter <u>5"</u> Length of casing _____	Pumping rate _____ G.P.M. Duration of test _____ hrs.
Type of screen <u>4" Everdur</u> Length of screen <u>6 ft.</u>	Drawdown _____ ft. Date _____
Type of pump _____	Developed capacity _____
Capacity of pump _____	Static level—depth to water _____ ft.
Depth of pump setting _____	Pump installed by _____
Date of completion <u>11-24-61</u>	

WELL LOG			SKETCH SHOWING LOCATION
Formations Sandstone, shale, limestone, gravel and clay	From	To	Locate in reference to numbered State Highways, St. Intersections, County roads, etc.
<u>TEST HOLE #3</u>	0 Feet	_____ Ft.	N.
Yellow Clay	0'	25'	<div style="display: flex; justify-content: space-between; align-items: center;"> W. <div style="font-size: 2em; font-family: cursive;">Refer Log 179978</div> E. </div>
Yellow Sandy Clay	25'	32'	
Blue Clay	32'	33'	
Coarse Gravel & Sand	33'	42'	
Coarse Sand, Some Gravel	42'	47'	
Fine Sand	47'	58'	
Coarse Sand, No Gravel	58'	63'	
Sand	63'	74'	
Coarse Sand	74'	78'	
Good Coarse Sand & Gravel	78'	85'	
Coarse Sand, Some Gravel	85'	90'	
Coarse Sand	90'	95'	
Good Sand & Gravel	95'	105'	
Coarse Gravel & Lime			
Boulders	105'	107½'	
Soapstone Rock	107½'	109½'	S.

See reverse side for instructions

Drilling Firm Diehl Pump & Supply Co.
Address 3985 Race Rd., Cinti. 11, Ohio

Date January 12, 1962
Signed Edward B. Wagner *64*
Diehl Pump & Supply Co., Inc.

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
1500 Dublin Road
Columbus, Ohio

SOIL BORING LOG 4

No. 179981

County Hamilton Township Miami Section of Township _____
Owner E. I. DuPont de Nemours & Co. Address Ft. Hill Plant, North Bend, Ohio
Location of property _____

CONSTRUCTION DETAILS

Casing diameter 5" Length of casing _____
Type of screen - Length of screen _____
Type of pump _____
Capacity of pump _____
Depth of pump setting _____
Date of completion 11-17-61

BAILING OR PUMPING TEST

Pumping rate _____ G.P.M. Duration of test _____ hrs.
Drawdown _____ ft. Date _____
Developed capacity _____
Static level—depth to water _____ ft.
Pump installed by _____

WELL LOG

Formations Sandstone, shale, limestone, gravel and clay	From	To
	0 Feet	_____ Ft.
<u>TEST HOLE #4</u>		
To Soil	0'	3'
Yellow Clay	3'	15'
Coarse Gravel	15'	20'
Coarse Dirty Gravel	20'	30'
Coarse Sand & Gravel	30'	32'
Fine Sand	32'	36'
Blue Clay	36'	38'
Fine Sand	38'	51'
Sand, Coarse	51'	55'
Coarse Sand, Some Gravel	55'	60'
Sand and Some Gravel	60'	63'
Sand and Some Gravel	63'	73'
Good Gravel, Some Sand	73'	87'
Sand, Gravel & Boulders	87'	90'
Rock	90'	92'

SKETCH SHOWING LOCATION

Locate in reference to numbered
State Highways, St. Intersections, County roads, etc.

N.

W. *Rfr Log 179978* E.

S.

See reverse side for instructions

Drilling Firm Diehl Pump & Supply Co.
Address 3985 Race Rd., Cinti. 11, Ohio

Date January 12, 1962
Signed *Edward F. Wagner*
Diehl Pump & Supply Co. Inc.

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
1500 Dublin Road
Columbus, Ohio

SOIL BORING LOG 5

No. 179982

County Hamilton Township Miami Section of Township

Owner E. I. DuPont de Nemours & Co. Address Ft. Hill Plant, North Bend, Ohio

Location of property

CONSTRUCTION DETAILS

Casing diameter 5" Length of casing
Type of screen 4" Everdur Length of screen 6 ft.
Type of pump
Capacity of pump
Depth of pump setting
Date of completion 11-21-61

BAILING OR PUMPING TEST

Pumping rate.....G.P.M. Duration of test.....hrs.
Drawdown.....ft. Date.....
Developed capacity.....
Static level—depth to water.....ft.
Pump installed by.....

WELL LOG

Formations Sandstone, shale, limestone, gravel and clay	From	To
<u>TEST HOLE #5</u>	0 FeetFt.
Soil, Clay	0'	15'
Blue Clay	15'	35'
Good Coarse Gravel & Sand	35'	52'
Sand	52'	62'
Coarse Sand	62'	68'
Good Coarse Gravel & Sand	68'	76'
Coarse Sand & Gravel	76'	87'
Rock	87'	89'

SKETCH SHOWING LOCATION

Locate in reference to numbered
State Highways, St. Intersections, County roads, etc.

N.

W.

E.

S.

See reverse side for instructions

Drilling Firm Diehl Pump & Supply Co.
Address 3985 Race Rd., Cinti. 11, Ohio

Date January 12, 1962

Signed

Edward P. Wagoner 62
Diehl Pump & Supply Co., Inc.

APPENDIX F

WELL LOGS OF THE AREA OF THE SITE

WEL' LOG AND DRILLING REPORT

NO CARBON PAPER
NECESSARY -
SELF-TRANSCRIBING

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Geological Survey
Fountain Square
Columbus, Ohio 43224 Phone

472225

COUNTY Hamilton TOWNSHIP ~~Jefferson~~ SECTION OF TOWNSHIP
OR LOT NUMBER _____
OWNER E. I. du Pont de Nemours & Company ADDRESS Fort Hill Plant, Brower Rd., N. Bend, Ohio
LOCATION OF PROPERTY 5 Miles South West of North Bend, Ohio

[illegible]

ILLING FIRM MOODY'S OF DAYTON, INC.
ADDRESS P.O. BOX 123, 4359 INFIRMARY RD.,
MIAMISBURG, OHIO 45342

DATE 22 April '77
SIGNED Charlie Buckner /S

*If additional space is needed to complete well log, use next consecutive numbered form.

WELL LOG 2

472209

CONSTRUCTION DETAILS	BAILING OR PUMPING TEST (specify one by circling)
Casing diameter <u>8"</u> Length of casing <u>113'</u>	Test rate <u>120</u> gpm Duration of test <u>10</u> hrs
Type of screen <u>Johnson S.S.</u> Length of screen <u>21'1"</u>	Drawdown <u>2'6"</u> ft Date <u>Dec. 1974</u>
Type of pump <u>---</u>	Static level (depth to water) <u>44'</u> ft
Capacity of pump <u>---</u>	Quality (clear, cloudy, taste, odor) <u>Clear</u>
Depth of pump setting <u>---</u>	
Date of completion <u>Dec. 20, 1974</u>	Pump installed by <u>---</u>

[illegible]

A hand-drawn map showing a site layout. The map is oriented with North (N) at the top, West (W) on the left, East (E) on the right, and South (S) at the bottom. A horizontal line at the top is labeled "N. Bend Road" on the left and "Cleve ->" on the right. A vertical line runs from the top center to the bottom center, labeled "Entrance Road" written vertically. At the bottom, a wavy line represents a "River". In the lower-left quadrant, there is a small circle labeled "well". In the lower-right quadrant, there is a rectangle labeled "Plant".

SIGNED

• If additional space is needed to complete well log, use next consecutive numbered form.

County Permit No.

WEL' LOG AND DRILLING REPORT

WELL LOG 3

NO CARBON PAPER
NECESSARY -
SELF-TRANSCRIBINGState of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
Fountain Square
Columbus, Ohio 43224

547528

COUNTY Hamilton TOWNSHIP Miami SECTION OF TOWNSHIP _____OWNER E. I. duPont de Nemours & Company ADDRESS North Bend, Ohio

County Permit No.

WEL' LOG AND DRILLING REPORT

ORIGINAL

NO CARBON PAPER
NECESSARY -
SELF-TRANSCRIBINGState of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
Fountain Square
Columbus, Ohio 43224

547529

COUNTY Hamilton TOWNSHIP Miami SECTION OF TOWNSHIP _____OWNER E. I. duPont de Nemours & Company ADDRESS North Bend, OhioLOCATION OF PROPERTY East of the confluence of the Ohio & Great Miami Rivers

CONSTRUCTION DETAILS

BAILING OR PUMPING TEST

(specify one by circling)

Casing diameter 20" Length of casing 58'Type of screen 36 x 20 gp s.s. Length of screen 25'Type of pump Byron Jackson submersibleCapacity of pump 750 GPM @ 350 TDHDepth of pump setting 70'Date of completion 3/5/80Test rate 1000 gpm Duration of test 24 hrsDrawdown 11' ft Date 5/29/80Static level (depth to water) 11'5" ftQuality (clear, cloudy, taste, odor) clear

Pump installed by _____

WELL # 50


WELL LOG*

Formations: sandstone, shale,
limestone, gravel, clay

From To

Top soil	0 ft	5 ft
Sandy clay	5	25
Grey clay & some gravel	25	30
Grey clay	30	35
Grey clay & med. gravel	35	40
Fine sand & med. gravel	40	60
Coarse gravel	60	70
Coarse gravel & fine sand	70	75
Medium gravel	75	80
Coal seam	80	81
Bedrock	81	85

SKETCH SHOWING LOCATION

Locate in reference to numbered
state highways, street intersections, county roads, etc.

WELL LOG AND DRILLING REPORT

PLEASE USE PENCIL
OR TYPEWRITER

DO NOT USE INK.

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
1562 W. First Avenue
Columbus, Ohio 43212

WELL LOG 4
Nº 348946

County HAMILTON Township Miami Section of Township _____
Owner CHEVRON ASPHALT CO Address BOX 38014 CINCINNATI, O.
Location of property 11001 BROWER ROAD

CONSTRUCTION DETAILS

Casing diameter 16 Length of casing 100'
Type of screen WIRE WOUND Length of screen 20'
Type of pump VERTICAL TURBINE
Capacity of pump 400 GPM
Depth of pump setting 98'-10 1/2"
Date of completion NOV. 27, 1972

BAILING OR PUMPING TEST


Pumping Rate 454 G.P.M. Duration of test 24 hrs.
Drawdown ? ft. Date 12/14/72
Static level-depth to water 54'-4" ft.
Quality (clear, cloudy, taste, odor) CLEAR -
ODORLESS - TASTELESS
Pump installed by DIETL PUMP

WELL LOG*

Formations Sandstone, shale, limestone, gravel and clay	From	To
<u>ASPHALT</u>	<u>0 Feet</u>	<u>1 Ft.</u>
<u>OVERLAY</u>	<u>1'</u>	<u>50'</u>
<u>BROWN MUD</u>	<u>50'</u>	<u>70'</u>
<u>FINE SAND</u>	<u>70'</u>	<u>85'</u>
<u>FINE SAND SM. GR.</u>	<u>85'</u>	<u>95'</u>
<u>" " MED GR</u>	<u>95'</u>	<u>100'</u>
<u>MED. COARSE SAND</u>	<u>100'</u>	<u>111'</u>
<u>COARSE SAND</u>	<u>111'</u>	<u>120'</u>
<u>BLUE CLAY</u>	<u>120'</u>	

SKETCH SHOWING LOCATION

Locate in reference to numbered
State Highways, St. Intersections, County roads, etc.



Drilling Firm DIETL PUMP Date 12/18/72 30
Address 550 N. WAYNE AVE Signed L F Brewer
CINCINNATI, O. 45215

*If additional space is needed to complete well log, use next consecutive numbered form.

WEL' LOG AND DRILLING REPORT

NO CARBON PAPER
NECESSARY -
SELF-TRANSCRIBING

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Geological Survey
Fountain Square
Columbus, Ohio 43224 Phone

472225

COUNTY Hamilton TOWNSHIP Jefferson SECTION OF TOWNSHIP _____
OR LOT NUMBER _____
OWNER E. I. du Pont de Nemours & Company ADDRESS Fort Hill Plant, Brower Rd., N. Bend, Ohio
LOCATION OF PROPERTY 5 Miles South West of North Bend, Ohio

CONSTRUCTION DETAILS			BAILING OR PUMPING TEST (specify one by circling)	
Casing diameter _____ 12" _____	Length of casing _____ 98'-4" _____		Test rate _____ 617 _____ gpm	Duration of test _____ 6 _____ hrs
Type of screen _____ Cook S. S. _____	Length of screen _____ 25'-8" _____		Drawdown _____ 15'7" _____ ft	Date _____ 4-11-77 _____
Type of pump _____ B-J 10 MQL-7 Stage _____			Static level (depth to water) _____ 42'5" _____ ft	
Capacity of pump _____ 500 gpm @ 285-ft. TDH _____			Quality (clear, cloudy, taste, odor) _____ Good _____	
Depth of pump setting _____ 147'-2" _____			Pump installed by _____ Moody's of Dayton, Inc. _____	
Date of completion _____ March 30, 1977 _____				
WELL # 37	WELL LOG*		SKETCH SHOWING LOCATION	
Formations: sandstone, shale, limestone, gravel, clay	From	To	Locate in reference to numbered state highways, street intersections, county roads, etc.	
Broken Concrete Fill	0 ft	4 ft	<p>N</p> <p>BROWER RD</p> <p>WELL</p> <p>Railroad</p> <p>S</p> <p>E</p> <p>PLANT & BLDGS.</p>	
Clay	4	12		
Coarse Gravel & Sand	12	25		
Medium Gravel & Sand	25	50		
Clay	50	65		
Gravel, Sand & Clay	65	80		
Medium Gravel	80	124		

ILLING FIRM MOODY'S OF DAYTON, INC.
ADDRESS P.O. BOX 123, 4359 INFIRMARY RD.,
MIAMISBURG, OHIO 45342

DATE 22 April '77
SIGNED Charlie Buckner /S

*If additional space is needed to complete well log, use next consecutive numbered form.

Appendix F

AREA Soil Borings

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
1500 Dublin Road
Columbus, Ohio

No. 179978

County Hamilton Township Miami Section of Township _____
Owner E. I. DuPont de Nemours & Co. Address Ft. Hill Plant, North Bend, Ohio
Location of property _____

CONSTRUCTION DETAILS

Casing diameter 5" Length of casing _____
Type of screen 1" Everdun Length of screen 6 ft.
Type of pump _____
Capacity of pump _____
Depth of pump setting _____
Date of completion _____

BAILING OR PUMPING TEST


Pumping rate _____ G.P.M. Duration of test _____ hrs.
Drawdown _____ ft. Date _____
Developed capacity _____
Static level—depth to water _____ ft.
Pump installed by _____

WELL LOG

Formations Sandstone, shale, limestone, gravel and clay	From	To
<u>TEST HOLE #1</u>	0 Feet	_____ Ft.
Top Soil	0'	5'
Yellow Clay	5'	10'
Clay, Some Gravel	10'	16'
Coarse Gravel & Boulders	16'	24'
Clay	24'	28'
Sand, Some Gravel	28'	39'
Clay	39'	40'
Fine Dirty Sand, Some Gravel	40'	50'
Dirty Sand	50'	75'
Good Coarse Gravel	75'	79'
Sand and Gravel	79'	85'
Coarse Sand & Gravel	85'	90'
Good Coarse Sand & Gravel	90'	97'
Coarse Gravel, Some Sand	97'	100'
Gravel and Boulders	100'	101'
Rock	101'	103'

SKETCH SHOWING LOCATION

Locate in reference to numbered
State Highways, St. Intersections, County roads, etc.



See reverse side for instructions

Drilling Firm Diehl Pump & Supply Co., Inc Date January 12, 1962

Address 2985 Race Road, Cinti. 11, Ohio

Signed

Edward B. Wagner
Diehl Pump & Supply Co. Inc.

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
1500 Dublin Road
Columbus, Ohio

No. 179979

County Hamilton Township Miami Section of Township _____

Owner E. I. DuPont de Nemours & Co. Address Ft. Hill Plant, North Bend, Ohio

Location of property _____

CONSTRUCTION DETAILS

Casing diameter 5" Length of casing _____

Type of screen - Length of screen -

Type of pump -

Capacity of pump _____

Depth of pump setting _____

Date of completion 11-15-61

BAILING OR PUMPING TEST

Pumping rate _____ G.P.M. Duration of test _____ hrs.

Drawdown _____ ft. Date _____

Developed capacity _____

Static level—depth to water _____ ft.

Pump installed by _____

WELL LOG

Formations Sandstone, shale, limestone, gravel and clay	From	To
<u>TEST HOLE #2</u>	0 Feet	_____ Ft.
Soil & Clay	0'	15'
Yellow Clay	15'	20'
Clay	20'	25'
Coarse Dirty Gravel	25'	30'
Coarse Gravel	30'	38'
Clay	38'	41'
Sandy Clay & Gravel	41'	45'
Sand	45'	50'
Coarse Sand	50'	58'
Coarse Sand, Some Gravel	58'	75'
Coarse Sand	75'	80'
Good Coarse Sand & Gravel	80'	85'
Coarse Sand and Gravel	85'	90'
Good Coarse Gravel & Sand	90'	98½'
Rock	98½'	100½'

SKETCH SHOWING LOCATION

Locate in reference to numbered
State Highways, St. Intersections, County roads, etc.

N.

W.

E.

S.

See reverse side for instructions

Drilling Firm Diehl Pump & Supply Co.

Address 3985 Race Rd., Cinti. 11, Ohio

Date January 12, 1962

Signed _____

Edward B. Wagner 65
Diehl Pump & Supply Co. Inc.

State of Ohio
DEPARTMENT OF NATURAL RESOURCES

Division of Water
1500 Dublin Road
Columbus, Ohio

No. 179980

County Hamilton Township Miami Section of Township _____
Owner E. I. duPont Denemours & Co. Address Ft. Hill Plant, North Bend, Ohio
Location of property _____

CONSTRUCTION DETAILS	BAILING OR PUMPING TEST
Casing diameter <u>5"</u> Length of casing _____	Pumping rate _____ G.P.M. Duration of test _____ hrs.
Type of screen <u>4" Everdun</u> Length of screen <u>6 ft.</u>	Drawdown _____ ft. Date _____
Type of pump _____	Developed capacity _____
Capacity of pump _____	Static level—depth to water _____ ft.
Depth of pump setting _____	Pump installed by _____
Date of completion <u>11-24-61</u>	

WELL LOG			SKETCH SHOWING LOCATION
Formations Sandstone, shale, limestone, gravel and clay	From	To	<p align="center">Locate in reference to numbered State Highways, St. Intersections, County roads. etc.</p> <p align="center">N.</p> <div style="text-align: center; height: 150px;"> </div> <p align="center">S.</p>
<u>TEST HOLE #3</u>	<u>0 Feet.</u>	<u>_____ Ft.</u>	
Yellow Clay	0'	25'	
Yellow Sandy Clay	25'	32'	
Blue Clay	32'	33'	
Coarse Gravel & Sand	33'	42'	
Coarse Sand, Some Gravel	42'	47'	
Fine Sand	47'	58'	
Coarse Sand, No Gravel	58'	63'	
Sand	63'	74'	
Coarse Sand	74'	78'	
Good Coarse Sand & Gravel	78'	85'	
Coarse Sand, Some Gravel	85'	90'	
Coarse Sand	90'	95'	
Good Sand & Gravel	95'	105'	
Coarse Gravel & Lime			
Boulders	105'	107½'	
Soapstone Rock	107½'	109½'	

See reverse side for instructions

Drilling Firm Diehl Pump & Supply Co. Date January 12, 1962
Address 3985 Race Rd., Cinti. 11, Ohio Signed Edward B. Wagner *64*
Diehl Pump & Supply Co., Inc.

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
1500 Dublin Road
Columbus, Ohio

No. 179981

County Hamilton Township Miami Section of Township _____
Owner E. I. DuPont de Nemours & Co. Address Ft. Hill Plant, North Bend, Ohio
Location of property _____

CONSTRUCTION DETAILS	BAILING OR PUMPING TEST
Casing diameter <u>5"</u> Length of casing _____	Pumping rate _____ G.P.M. Duration of test _____ hrs.
Type of screen <u>-</u> Length of screen _____	Drawdown _____ ft. Date _____
Type of pump _____	Developed capacity _____
Capacity of pump _____	Static level—depth to water _____ ft.
Depth of pump setting _____	Pump installed by _____
Date of completion <u>11-17-61</u>	

WELL LOG			SKETCH SHOWING LOCATION
Formations Sandstone, shale, limestone, gravel and clay	From	To	Locate in reference to numbered State Highways, St. Intersections, County roads, etc.
<u>TEST HOLE #4</u>	0 Feet	_____ Ft.	N.
To Soil	0'	3'	<div style="display: flex; justify-content: space-between;"> W. Rfr Log 179978 E. </div>
Yellow Clay	3'	15'	
Coarse Gravel	15'	20'	
Coarse Dirty Gravel	20'	30'	
Coarse Sand & Gravel	30'	32'	
Fine Sand	32'	36'	
Blue Clay	36'	38'	
Fine Sand	38'	51'	
Sand, Coarse	51'	55'	
Coarse Sand, Some Gravel	55'	60'	
Sand and Some Gravel	60'	63'	S.
Sand and Some Gravel	63'	73'	
Good Gravel, Some Sand	73'	87'	
Sand, Gravel & Boulders	87'	90'	
Rock	90'	92'	See reverse side for instructions

Drilling Firm Diehl Pump & Supply Co.
Address 3985 Race Rd., Cinti. 11, Ohio

Date January 12, 1962
Signed Edward B. Wagner
Diehl Pump & Supply Co. Inc.

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
1500 Dublin Road
Columbus, Ohio

No. 179982

County Hamilton Township Miami Section of Township _____
Owner E. I. DuPont de Nemours & Co. Address Ft. Hill Plant, North Bend, Ohio
Location of property _____

CONSTRUCTION DETAILS

Casing diameter 5" Length of casing _____
Type of screen 4" Everdur Length of screen 6 ft.
Type of pump _____
Capacity of pump _____
Depth of pump setting _____
Date of completion 11-21-61

BAILING OR PUMPING TEST

Pumping rate _____ G.P.M. Duration of test _____ hrs.
Drawdown _____ ft. Date _____
Developed capacity _____
Static level—depth to water _____ ft.
Pump installed by _____

WELL LOG

Formations Sandstone, shale, limestone, gravel and clay	From	To
<u>TEST HOLE #5</u>	0 Feet	_____ Ft.
Soil, Clay	0'	15'
Blue Clay	15'	35'
Good Coarse Gravel & Sand	35'	52'
Sand	52'	62'
Coarse Sand	62'	68'
Good Coarse Gravel & Sand	68'	76'
Coarse Sand & Gravel	76'	87'
Rock	87'	89'

SKETCH SHOWING LOCATION

Locate in reference to numbered
State Highways, St. Intersections, County roads, etc.

N.

W.

E.

S.

See reverse side for instructions

Drilling Firm Diehl Pump & Supply Co.
Address 3985 Race Rd., Cinti. 11, Ohio

Date January 12, 1962

Signed

Edward P. Wagoner 62
Diehl Pump & Supply Co., Inc.

[illegible]

County Permit No. _____

WEL' LOG AND DRILLING REPORT

ORIGINAL

NO CARBON PAPER
NECESSARY -
SELF-TRANSCRIBINGState of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
Fountain Square
Columbus, Ohio 43224


547503

COUNTY Hamilton TOWNSHIP Miami SECTION OF TOWNSHIP _____OWNER E. I. DuPont de Nemours & Company ADDRESS North Bend, OhioLOCATION OF PROPERTY 4½ miles down river from North Bend on Brower Road**CONSTRUCTION DETAILS**Casing diameter 20" Length of casing 105'9½"
Type of screen S.S.-P.S. Cook Length of screen 26'8½"
Type of pump vertical turbine water lube
Capacity of pump 760 gpm
Depth of pump setting 110'
Date of completion 3-30-79**BAILING OR PUMPING TEST**

(specify one by circling)

Test rate 760 gpm Duration of test _____ hrs
Drawdown 34 ft Date April 3, 1979
Static level (depth to water) 44' (from top of casing) ft
Quality (clear, cloudy, taste, odor) clear
Pump installed by Moody's of Dayton (E. Wheeler)**WELL LOG***

Formations: sandstone, shale, limestone, gravel, clay	From	To
Hard dense clay	0 ft	4 ft
Sand & gravel	4	10
Coarse sand, med. gravel, some 5-6" boulders	10	43
Smooth yellow clay	43	86
Med. sand with small to med gravel	86	89
Grey sandy clay	89	91
Rough buried river bank veg- itation with wood & coal	91	93
Sand & gravel with clay	93	96
Med. to coarse sand, small to coarse gravel, some 5-6" boulders	96	115
Coarse sand, large blue gravel	115	131
Blue shale	131	132

SKETCH SHOWING LOCATIONLocate in reference to numbered
state highways, street intersections, county roads, etc.DRILLING FIRM Moody's of Dayton, Inc.DATE April 3, 1979ADDRESS 4359 Infirmary Rd., P.O. Box 123
Miamisburg, Ohio 45342SIGNED William R. Bastin
William R. Bastin

*If additional space is needed to complete well log, use next consecutive numbered form.

WELL LOG AND DRILLING REPORT

ORIGINAL

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
1500 Dublin Road
Columbus, Ohio

No. 179982

County Hamilton Township Miami Section of Township _____
Owner E. I. DuPont de Nemours & Co. Address Ft. Hill Plant, North Bend, Ohio
Location of property _____

CONSTRUCTION DETAILS	BAILING OR PUMPING TEST
Casing diameter <u>5"</u> Length of casing _____	Pumping rate _____ G.P.M. Duration of test _____ hrs.
Type of screen <u>4" Everdur</u> Length of screen <u>6 ft.</u>	Drawdown _____ ft. Date _____
Type of pump _____	Developed capacity _____
Capacity of pump _____	Static level—depth to water _____ ft.
Depth of pump setting _____	Pump installed by _____
Date of completion <u>11-21-61</u>	

WELL LOG			SKETCH SHOWING LOCATION
Formations Sandstone, shale, limestone, gravel and clay	From	To	Locate in reference to numbered State Highways, St. Intersections, County roads, etc.
<u>TEST HOLE #5</u>	0 Feet	_____ Ft.	N.
Top Soil, Clay	0'	15'	
Blue Clay	15'	35'	
Good Coarse Gravel & Sand	35'	52'	
Sand	52'	62'	
Coarse Sand	62'	68'	
Good Coarse Gravel & Sand	68'	76'	
Coarse Sand & Gravel	76'	87'	
Rock	87'	89'	
			W. <i>Rfr Log 179978</i> E.
			S.

See reverse side for instructions

Drilling Firm Diehl Pump & Supply Co.
Address 3985 Race Rd., Cinti. 11, Ohio

Date January 12, 1962
Signed Edward B. Wagner 62
Diehl Pump & Supply Co., Inc.

WELL LOG AND DRILLING REPORT

ORIGINAL

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
1500 Dublin Road
Columbus, Ohio

No. 179981

County Hamilton Township Miami Section of Township _____
Owner E. I. DuPont de Nemours & Co. Address Ft. Hill Plant, North Bend, Ohio
Location of property _____

CONSTRUCTION DETAILS		BAILING OR PUMPING TEST	
Casing diameter <u>5"</u>	Length of casing _____	Pumping rate _____ G.P.M.	Duration of test _____ hrs.
Type of screen _____	Length of screen _____	Drawdown _____ ft.	Date _____
Type of pump _____		Developed capacity _____	
Capacity of pump _____		Static level—depth to water _____ ft.	
Depth of pump setting _____		Pump installed by _____	
Date of completion <u>11-17-61</u>			

WELL LOG			SKETCH SHOWING LOCATION	
Formations Sandstone, shale, limestone, gravel and clay	From	To	Locate in reference to numbered State Highways, St. Intersections, County roads, etc.	
<u>TEST HOLE #4</u>	0 Feet	_____ Ft.	<u>N.</u>	
Top Soil	0'	3'	<div style="display: flex; justify-content: space-between;"> W. <i>Rfr Log 179978</i> E. </div>	
Yellow Clay	3'	15'		
Coarse Gravel	15'	20'		
Coarse Dirty Gravel	20'	30'		
Coarse Sand & Gravel	30'	32'		
Fine Sand	32'	36'		
Blue Clay	36'	38'		
Fine Sand	38'	51'		
Sand, Coarse	51'	55'		
Coarse Sand, Some Gravel	55'	60'		
Sand and Some Gravel	60'	63'	<div style="display: flex; justify-content: space-between;"> <u>S.</u> </div>	
Sand and Some Gravel	63'	73'		
Good Gravel, Some Sand	73'	87'		
Sand, Gravel & Boulders	87'	90'		
Rock	90'	92'	See reverse side for instructions	

Drilling Firm Diehl Pump & Supply Co.
Address 3985 Race Rd., Cinti. 11, Ohio

Date January 12, 1962
Signed Edward B. Wagner
Diehl Pump & Supply Co. Inc.

WELL LOG AND DRILLING REPORT

ORIGINAL

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
1500 Dublin Road
Columbus, Ohio

No. 179980

County Hamilton Township Miami Section of Township _____
Owner E. I. duPont Denemours & Co. Address Ft. Hill Plant, North Bend, Ohio
Location of property _____

CONSTRUCTION DETAILS			BAILING OR PUMPING TEST	
Casing diameter <u>5"</u> Length of casing _____	Pumping rate _____ G.P.M. Duration of test _____ hrs.			
Type of screen <u>4" Everdur</u> Length of screen <u>6 ft.</u>	Drawdown _____ ft. Date _____			
Type of pump _____	Developed capacity _____			
Capacity of pump _____	Static level—depth to water _____ ft.			
Depth of pump setting _____	Pump installed by _____			
Date of completion <u>11-24-61</u>				
WELL LOG			SKETCH SHOWING LOCATION	
Formations Sandstone, shale, limestone, gravel and clay	From	To	Locate in reference to numbered State Highways, St. Intersections, County roads, etc.	
<u>TEST HOLE #3</u>	0 Feet	Ft.	N.	
Yellow Clay	0'	25'	<div style="display: flex; justify-content: space-between; align-items: center;"> W. <div style="text-align: center; flex-grow: 1;"> <i>Refer Log 179978</i> </div> E. </div> <div style="text-align: center; margin-top: 100px;">S.</div>	
Yellow Sandy Clay	25'	32'		
Blue Clay	32'	33'		
Coarse Gravel & Sand	33'	42'		
Coarse Sand, Some Gravel	42'	47'		
Fine Sand	47'	58'		
Coarse Sand, No Gravel	58'	63'		
Sand	63'	74'		
Coarse Sand	74'	78'		
Good Coarse Sand & Gravel	78'	85'		
Coarse Sand, Some Gravel	85'	90'		
Coarse Sand	90'	95'		
Good Sand & Gravel	95'	105'		
Coarse Gravel & Lime	105'	107½'		
Boulders	107½'	109½'		
Soapstone Rock				
			See reverse side for instructions	

Drilling Firm Diehl Pump & Supply Co.
Address 3985 Race Rd., Cinti. 11, Ohio

Date January 12, 1962
Signed Edward B. Wagner *64*
Diehl Pump & Supply Co., Inc.

WELL LOG AND DRILLING REPORT

ORIGINAL

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
1500 Dublin Road
Columbus, Ohio

No. 179979

County Hamilton Township Miami Section of Township _____

Owner E. I. DuPont de Nemours & Co. Address Ft. Hill Plant, North Bend, Ohio

Location of property _____

CONSTRUCTION DETAILS	BAILING OR PUMPING TEST
Casing diameter <u>5"</u> Length of casing _____	Pumping rate _____ G.P.M. Duration of test _____ hrs.
Type of screen _____ Length of screen _____	Drawdown _____ ft. Date _____
Type of pump _____	Developed capacity _____
Capacity of pump _____	Static level—depth to water _____ ft.
Depth of pump setting _____	Pump installed by _____
Date of completion <u>11-15-61</u>	

WELL LOG			SKETCH SHOWING LOCATION
Formations Sandstone, shale, limestone, gravel and clay	From	To	Locate in reference to numbered State Highways, St. Intersections, County roads, etc.
<u>TEST HOLE #2</u>	0 Feet	_____ Ft.	N.
Top Soil & Clay	0'	15'	
Yellow Clay	15'	20'	
Clay	20'	25'	
Coarse Dirty Gravel	25'	30'	
Coarse Gravel	30'	38'	
Clay	38'	41'	
Sandy Clay & Gravel	41'	45'	
Sand	45'	50'	
Coarse Sand	50'	58'	
Coarse Sand, Some Gravel	58'	75'	
Coarse Sand	75'	80'	
Good Coarse Sand & Gravel	80'	85'	
Coarse Sand and Gravel	85'	90'	
Good Coarse Gravel & Sand	90'	98½'	
Rock	98½'	100½'	
			W. <i>Refer Log 179978</i> E.
			S.

See reverse side for instructions

Drilling Firm Diehl Pump & Supply Co.

Date January 12, 1962

Address 3985 Race Rd., Cinti. 11, Ohio

Signed

Edward B. Wagner 65
Diehl Pump & Supply Co. Inc.

ORIGINAL

No. 179978

Drilling Firm Diehl Pump & Supply Co., Inc. Date January 12, 1962
Address 2985 Race Road, Cinti. 11, Ohio Signed Edward B. Wagner
Diehl Pump & Supply Co. Inc.

OHIO WATER SUPPLY BOARD

Well Record No...124

Co. Hamilton Twp. Miami Sec.
Well Location West of Plant Size 26"
Map Lawrenceburg

Owner Cum. Gas & Elec. Co. Address Columbia Sta.
Driller Layne-Ohio Date 9-1-37

Well Head Elev. or M. P.
Elev. of Ground at Well

Pumping Test: 1500 GPM Pumping Level 50'

Static Level 36' Date

Normal Pumpage 1000 GPM

Quality Use

Adequacy of supply

Owner's Well No. or Other Designation 2A Replacement



Source of Data Layne-Ohio

Collected by Ramsay Date 8/18/42

STRATA	DEPTH	
	From	To
Top Soil	0	6
Wet Sandy Clay	6	42
Clay & Hardpan	42	54
Coarse Sand	54	108
Boulders	108	110
Rock	110	

• Chief Aquifer

X 1,347,900
Y 414,000



Deepwell # 2A

ABANDONED

NO LONGER IN SERVICE

Miami Fort Station

Cum. Gas & Electric

Braver Road

Near North Bend, OH

460
110
350
NTA 7-20-43

OHIO WATER RESOURCES BOARD

Well Record No. 468

Co. Hamilton Twp. 31 18 Sec. 18
Well Location Lawrenceburg Size 26" & 38"
Map Lawrenceburg

Owner Cincinnati Gas & Elec. Co Address Columbia Park, Ohio
Driller Layne Date 7/18/48

Well Head Elev. or M. P.
Elev. of Ground at Well

Pumping Test: 7/16/48 14 ft. D.D. 1000

Static Level 55 ft. Date 7/18/48
Normal Pumpage

Quality Use

Adequacy of supply

Owner's Well No. or Other Designation 4

Source of Data Layne

Collected by Date Jan. 1949

STRATA	DEPTH	
	From	To
Yellow clay Sand, clay & boulders Dry gravel Sand (water) Sand & boulders Gravel	0	
SIZE: 26" X 98' SIZE: 38" X 79½' Screen: 26" X 25' Capacity: 1000 G.P.M.		

x 1,377,000
y 4,000,000

• Chief Aquifer

DEEPWELL #4
(ABANDONED,
NO LONGER
IN SERVICE)

Miami Fort Station
Cint. Gas & Electric
Brower Road
Near North Bend, OH

458
21
DPA 7-29-8

ORIGINAL

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
65 S. Front St., Rm. 815 Phone (614) 469-2646
Columbus, Ohio 43215

450817

Owner Cincinnati Gas & Electric Address Miami Fort Station
North Bend, Ohio

Location of property.....

BAILING OR PUMPING TEST
(Specify one by circling)

Test Rate 1016 G.P.M. Duration of test _____ hrs.
Drawdown 11 ft. Date _____
Static level-depth to water 39 ft.
Quality (clear, cloudy, taste, odor) _____
Pump installed by _____

SKETCH SHOWING LOCATION

**Locate in reference to numbered
State Highways, St. Intersections, County roads, etc.**

N.

W.

E.

S.

Date August 1, 1974 ✓
Signed S. Couch & M. Garrison

***If additional space is needed to complete well log, use next consecutive numbered form.**

OHIO WATER SUPPLY BOARD

Well Record No. 122

Co. Hamilton Twp. Miami Sec. 26"
Well Location Columbia Power
Sta. on Ohio River Map Lawrenceburg

Owner Cinn. Gas & Elec. Co. Address Columbia Sta.
Driller Layne-Ohio Date Nov. 1937

Well Head Elev. or M. P.
Elev. of Ground at Well

Pumping Test: 1600 GPM Pumping Level 60'

Static Level 46' Date

Normal Pumpage 1000 GPM

Quality Use

Adequacy of supply

Owner's Well No. or Other Designation 2

Source of Data Layne-Ohio

Collected by Ramsay Date 8/15/42

STRATA	DEPTH	
	From	To
Top Soil	0	
Wet Sandy Clay	8	
Clay & Hardpan	40	
Fine & Coarse Sand	58	
Sand & Gravel	105	
Rock		

1,347,700
419,000
• Chief Aquifer



Deep well # 2

(ABANDONED, NO
LONGER IN SERVICE)

Miami Fort Station
Cinn. Gas & Electric
Brewer Rd.
Near North Bend, OH

PTA 7-29-83

23

485

WEI LOG AND DRILLING REPORT

ORIGINAL

NO CARBON PAPER
NECESSARY—
SELF-TRANSCRIBING

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
65 S. Front St., Rm. 815 Phone (614) 469-2646
Columbus, Ohio 43215

No. 407791

County Hamilton Township Miami Section of Township _____

Owner Cincinnati Gas & Elect. Co. Address North Bend Ohio

Location of property Miami Fort Sta - 30 ft west of No. 3 well

CONSTRUCTION DETAILS

Casing diameter 26" Length of casing 96'6"
Type of screen Shutter Length of screen 30'
Type of pump Layne
Capacity of pump 1000 GPM
Depth of pump setting 90'
Date of completion 9-2-72

BAILING OR PUMPING TEST
(Specify one by circling)

Test Rate 1000 G.P.M. Duration of test 10 hrs.
Drawdown 21 ft. Date _____
Static level-depth to water 41 ft.
Quality (clear, cloudy, taste, odor) _____
Pump installed by Layne Ohio Co.

WELL LOG*

SKETCH SHOWING LOCATION

Formations Sandstone, shale, limestone, gravel and clay	From	To
<u>Slag free</u>	<u>0 Feet</u>	<u>1.5 Ft.</u>
<u>Yellow clay</u>	<u>1.5</u>	<u>4.5</u>
<u>Yellow sand</u>	<u>4.5</u>	<u>112</u>
<u>Sand & Boulders</u>	<u>112</u>	<u>115</u>
<u>Gray clay</u>	<u>115</u>	<u>116</u>
<u>Sand, gravel & Boulders</u>	<u>116</u>	<u>125</u>
<u>Gray shale</u>	<u>125</u>	<u>126</u>

Locate in reference to numbered
State Highways, St. Intersections, County roads, etc.

N.

W.

E.

S.

Drilling Firm Layne Ohio Co.
Address Columbus, Ohio

Date 12-5-72
Signed Ob. McEntee
Layne Ohio Co.


*If additional space is needed to complete well log, use next consecutive numbered form.

OHIO WATER SUPPLY BOARD

Well Record No. 125


Co. Hamilton Twp. Miami Sec. _____
Well Location Columbia Power Sta. Size 26"
Map Lawrenceburg
Owner Cin. Gas & Elec. Co. Address Cincinnati, O.
Driller Layne-Ohio Date 1937
Well Head Elev. or M. P. _____
Elev. of Ground at Well _____
Pumping Test: 1250 GPM 12' Draw down
Static Level _____ Date _____
Normal Pumpage _____
Quality _____ Use _____
Adequacy of supply _____
Owner's Well No. or Other Designation 3
Source of Data Layne-Ohio
Collected by Rumsey Date 9/2/42

STRATA	DEPTH	
	From	To
Sandy Surface Soil Sand	0	20
X 1,347,900 Y 40,000		
* Chief Aquifer		



Deepwell #3

(ABANDONED,
NO LONGER
IN SERVICE)



Miami Fort Station
Cinti Gas & Electric
Brower Rd.
Near North Bend, Olt

OTA
1-29-83
500
114
25

OHIO WATER SUPPLY BOARD

Well Record No. 125

Co. Hamilton Twp. Miami Sec. 18
 Well Location Above Mouth of Miami Size 18"
 R. Lawrenceburg
 Union Gas & Elec. Co. Columbia
 Owner Eng'g. & Management Corp. Address. Columbia Park
 Driller Layne Date 11-27-34

Well Head Elev. or M. P.
 Elev. of Ground at Well

Pumping Test: 290 gpm - Guarantee 200 gpm - Pump.

Static Level 58' Date
 Normal Pumpage

Quality Use Industrial

Adequacy of supply

Owner's Well No. or Other Designation 1

Source of Data Layne



Collected by Ramsey Date 8-22-42

STRATA	DEPTH	
	From	To
Clay	0	1
Sandy Clay		2
Sand & Gravel		3
Sand		4
Sand & Gravel		5
Sand		6
Sand & Gravel		7
" " "		8
Level 65'		9

X 134,7900
 y 41,4000
 Columbia Park

* Chief Aquifer

Deepwell A.1



ABANDONED, NO LONGER
 IN SERVICE

Miami Fort Station
 Cinti Gas & Electric
 Brower Road
 Near North Bend, OH

490

DTA 7-29-83 26

WELL LOG AND DRILLING REPORT

ORIGINAL

State of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
1500 Dublin Road
Columbus, Ohio

No. 201695

Log 1279

County HAMILTON Township MIAMI Section of Township SW corner Sec 20

Owner CINCINNATI GAS & ELECTRIC CO Address CINCINNATI, O

Location of property Same

CONSTRUCTION DETAILS

Casing diameter Length of casing

Type of screen Length of screen

Type of pump

Capacity of pump

Depth of pump setting

Date of completion

BAILING OR PUMPING TEST

Pumping rate G.P.M. Duration of test hrs.

Drawdown ft. Date

Developed capacity

Static level—depth to water ft.

Pump installed by

WELL LOG

Formations
Sandstone, shale, limestone,
gravel and clay

From

0 Feet

To

..... Ft.

SKETCH SHOWING LOCATION

Locate in reference to numbered
State Highways, St. Intersections, County roads, etc.

N.

Well is located at
Columbia Park Station
in Ohio River valley
200 ft. Down stream
+ 200 ft. N of Ohio River

W.

E.

S.


See reverse side for instructions

Drilling Firm Loyne Ohio Co

Address 1100 W Town St

Date 11-4-57

Signed L. H. Huns



MATERIAL:

Pit: 84' of 38" x 3/8" Steel Casing & 96' of 26" x 3/8" Casing.

Screen: 25' of 26" Stainless Steel Screen.

Cone: 26" x 34" x 2' Steel Cone.

PUMP:

No.	33048	Shop No.	33048
Type	D. R. H. C.	Size	15"
Setting	100'	Stages	6
Suction	8" x 7-5" Long	Impellers	Bronze
Discharge	8"	Head	
Tubing	3"	Press. B. P.	
Shafting	1 1/2" / 16		

MOTOR:

Make	U. S.	Type	C. F. U.
Volts	2300	Cycle	60
Phase	3	Amp.	
H. P.	100	R. P. M.	1200
Frame	587-P	Serial	

WELL:

Capacity	1000 G. P. M.	Static Level	69'
Guarantee	1000 G. P. M.	P. Level	80'
Started	7-29-55	Pressure	
Finished	9-23-55	Pumped	1000 G. P. M.
Accepted	9-23-55	Depth	111'

REMARKS:

Driller: Reuben Sawyers
Installer: Gerald Harid

THE LAYNE-OHIO CO.,

WATER SUPPLY CONTRACTORS

COLUMBUS

OHIO

CINCINNATI GAS
& ELECTRIC CO.

COLUMBIA PARK - OHIO

DRAWN BY O. L. MS

APPROVED BY

WELL NO

5

DRAWING NO

1279

WELL LOG AND DRILLING REPORT

State of Ohio
Department of Natural Resources
Division of Water
~~1562 N. Broad Avenue~~
Columbus, Ohio

PT. OF NATURAL RESOURCES
DIVISION OF WATER
815 OHIO DEPARTMENT'S BLDG.
COLUMBUS, OHIO 43215

LAYNE # 1279

NO. 201695

County HAMILTON Township MIAMI Section of Township _____Owner CINCINNATI GAS & ELECTRIC CO. Address CINCINNATI, OLocation of property COLUMBIA PARK STATION IN OHIO RIVER VALLEY200 FT NORTH OF OHIO RIVER

CONSTRUCTION DETAILS

BAILING OR PUMPING TEST

Casing diameter 36" Length of casing 84' Pumping rate 1000 G.P.M.Type of screen 26" S.S. Length of screen 96' Duration of test - Hrs.Type of pump D.R.H.C. Drawdown 11 ft. Date _____Capacity of pump _____ Static level - depth to water 69 Ft.Depth of pump setting 100 Quality _____Date of completion 9-23-55 Pump installed by LAYNE - OHIO

WELL LOG

SKETCH SHOWING LOCATION

Formation	From	To	N.	E.
TOP SOIL	0	2		
YELLOW CLAY	2	12		
SANDY CLAY	12	30		
BLUE SANDY CLAY	30	33		
COARSE SAND & GRAVEL	33	39	W.	
DIRTY SAND & GRAVEL	39	45		
SAND & BOULDERS	45	60		
SAND & GRAVEL	60	63		
SAND (LITTLE GRAVEL)	63	107		
BOULDERS & GRAVEL	107	110		
BLUE CLAY	110	111		
HARD SHALE	111	-		

26" x 34" x 2' STEEL CONE
PLUS CEMENT PLUG AT 111'

S.

Drilling Firm LAYNE - OHIO Date 7-29-55Address COLUMBUS OHIO Copied by J.A.N.


OHIO WATER RESOURCES BOARD

Well Record No. 469

Co. Hamilton Twp. 119 mi Sec. 18
 Well Location 18" & 38"
 Map Lawrenceburg
 Owner Cincinnati Gas & Elec. Co. Address Columbia Station
 Drilled Layne Date 8/12/48
 Well Head Elev. or M. P. _____
 Elev. of Ground at Well _____
 Pumping Test: 5 ft. D.D. 200
 Static Level 54 ft. Date 8/12/48
 Normal Pumpage _____
 Quality _____ Use _____
 Adequacy of supply _____
 Owner's Well No. or Other Designation _____
 Source of Data Layne
 Collected by _____ Date Jan. 1949

STRATA	DEPTH	
	From	To
Yellow clay Dry dirty gravel Dry sand Sand & gravel (water) Sand, gravel & boulders	0	3
SIZE: 18" X 88' SIZE: 38" X 69' Screen: 18" X 20' Capacity: 200 G.P.M.		


X 1347.900
 Y 414.000
 • Chief Aquifer



DEEPWELL #5

*(ABANDONED,
 NO LONGER IN
 SERVICE)*

Miami Fort Station
 Cinti Gas & Electric
 Brower Rd.
 Near North Bend, OH



ONE

7-29-83

47

28

ORIGINAL

472209

*If additional space is needed to complete well log, use next consecutive numbered form.

WELL LOG AND DRILLING REPORT

ORIGINAL

State of Ohio

PLEASE USE PENCIL
OR TYPEWRITER

DEPARTMENT OF NATURAL RESOURCES

Division of Water

1562 W. First Avenue
Columbus, Ohio 43212

No 348946

County HAMILTON Township Miami Section of Township _____

Owner CHEVRON ASPHALT CO Address BOX 38014 CINCINNATI, O.

Location of property 11001 BROWER ROAD

CONSTRUCTION DETAILS

Casing diameter 16 Length of casing 100'
Type of screen WIRE WOUND Length of screen 20'
Type of pump VERTICAL TURBINE
Capacity of pump 400 GPM
Depth of pump setting 98'-10 1/2"
Date of completion NOV. 27, 1972

BAILING OR PUMPING TEST


Pumping Rate 454 G.P.M. Duration of test 24 hrs.
Drawdown ? ft. Date 12/14/72
Static level-depth to water 54'-4" ft.
Quality (clear, cloudy, taste, odor) CLEAR -
ODORLESS - TASTELESS
Pump installed by DIEHL PUMP

WELL LOG*

Formations Sandstone, shale, limestone, gravel and clay	From	To
<u>ASPHALT</u>	<u>0 Feet</u>	<u>1 Ft.</u>
<u>OVERLAY</u>	<u>1'</u>	<u>50'</u>
<u>BROWN MUD</u>	<u>50'</u>	<u>70'</u>
<u>FINE SAND</u>	<u>70'</u>	<u>85'</u>
<u>FINE SAND SM. GR.</u>	<u>85'</u>	<u>95'</u>
<u>" " MED GR</u>	<u>95'</u>	<u>100'</u>
<u>MED. COARSE SAND</u>	<u>100'</u>	<u>111'</u>
<u>COARSE SAND</u>	<u>111'</u>	<u>120'</u>
<u>BLUE CLAY</u>	<u>120'</u>	

SKETCH SHOWING LOCATION

Locate in reference to numbered
State Highways, St. Intersections, County roads, etc.



See reverse side for instructions

Drilling Firm DIEHL PUMP

Date 12/18/72 30

Address 550 N. WAYNE AVE
CINCINNATI, O. 45215

Signed L F Brewer

*If additional space is needed to complete well log, use next consecutive numbered form.

OWNER Chevron Asphalt Co ADDRESS Brower 14 North Venice, FL
 LOCATION OF PROPERTY Next to C64E Miami Fort Station

CONSTRUCTION DETAILS

Casing diameter 16" Length of casing 89
 Type of screen _____ Length of screen See below
 Type of pump Turbine
 Capacity of pump 500 gpm
 Depth of pump setting 85'
 Date of completion 5/21/74

BAILING OR PUMPING TEST (specify one by circling)


Test rate 1200 gpm Duration of test _____ hrs
 Drawdown 2 Air ft Date 5/16/74
 Static level (depth to water) 42'6" ft
 Quality (clear, cloudy, taste, odor) Clear
 Pump installed by W Crane

WELL LOG*

Formations: sandstone, shale, limestone, gravel, clay	From	To
<u>Dirty sand</u>	<u>0 ft</u>	<u>3 ft</u>
<u>Dirty sand & gravel</u>	<u>3</u>	<u>55</u>
<u>Sand & med gravel</u>	<u>55</u>	<u>80</u>
<u>Med sand & gravel</u>	<u>80</u>	<u>95</u>
<u>Fine sand & med sand & gravel</u>	<u>95</u>	<u>110</u>
<u>Coarse gravel</u>	<u>110</u>	<u>114</u>
<u>Clay & gravel</u>	<u>114</u>	<u>—</u>
<u>Bottomed at 114'</u>		
<u>STRAINER</u>		
<u>25 FT 12" stainless steel Cook</u>		
<u>Strainer #9 wire with 16" packer as</u>		
<u>follows Top 6'</u>	<u>#60</u>	
<u>Next 7'</u>	<u>#40</u>	
<u>Next 10'</u>	<u>#30</u>	
<u>Bottom 2'</u>	<u>#80</u>	

SKETCH SHOWING LOCATION

Locate in reference to numbered state highways, street intersections, county roads, etc.



DRILLING FIRM

W M Crane

ADDRESS

Box 33 Shandon, O

DATE

7/10/74


SIGNED

W M Crane

*If additional space is needed to complete well log, use next consecutive numbered form.

Coordinates N. 34.0
E. 3314.0

0	Top Soil
5	Clay & Gravel
15	Dry Sand & Gravel
30	Clay & Gravel
50	Yellow Clay
53	Blue Clay
90	Brown Sand
95	Dirty Sand Clay & Gravel
100	Clay & Gravel
105	Gray Sand & Clay
110	Dirty Sand & Gravel
115	Blue Clay
122	



MATERIAL:

Pit: 122' of 26" Steel Casing & 123'-6" of 16" Steel Pipe.

Screen: 10'-6" of 16" O.D. Everdur Bronze Cook Screen, with #125 Slots.

Cone: Bronze Plate.

PUMP:

No.	34039	Shop No.	34039
Type	RKHC	Size	10"
Setting	115'	Stages	7
Suction	6" x 5"	Impellers	Bronze
Discharge	6"	Head	
Tubing	None	Press. B. P.	
Shafting	1 1/2"		

MOTOR: Steam Turbine

Make	Coppus-275*Psig.	Type	TFV 20
Volts		Cycle	
Phase		Amp.	
H. P.	50	R. P. M.	1800
Frame		Serial	

WELL:

Capacity	500 G.P.M.*	Static Level	455.6
Guarantee	None	P. Level	405.8
Started	3-8-56	Pressure	
Finished	4-3-56	Pumped	430 G.P.M.
Accepted	4-3-56	Depth	134'

REMARKS:

* Nominal pump capacity & Well capacity variable with ground water level.

Top of pump foundation El. 515.17

Driller: Toledo Rogers
Installer: Reuben Sawyers

Proj. 6396
Fort Hill
Fa. 500
Order GBC-3 1/2

THE LAYNE-OHIO CO.,

WATER SUPPLY CONTRACTORS

COLUMBUS

COLUMBUS

WELL LOG AND DRILLING REPORT

State of Ohio

DEPARTMENT OF NATURAL RESOURCES

Division of Geological Survey

Fountain Square

Columbus, Ohio 43224

Phone (614) 466-5344

470758

NO CARBON PAPER
NECESSARY—
SELF-TRANSCRIBING

SECTION OF TOWNSHIP
OR LOT NUMBER

36

COUNTY

Hamilton

TOWNSHIP

Miami

County Permit No. _____

WELL LOG AND DRILLING REPORT

ORIGINAL

NO CARBON PAPER
NECESSARY -
SELF-TRANSCRIBINGState of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
Fountain Square
Columbus, Ohio 43224

547528

COUNTY Hamilton TOWNSHIP Miami ? SECTION OF TOWNSHIP _____OWNER E. I. duPont de Nemours & Company ADDRESS North Bend, OhioLOCATION OF PROPERTY East of confluence of Ohio & Great Miami Rivers**CONSTRUCTION DETAILS**Casing diameter 20" Length of casing 68'Type of screen 36 x 20 gp S.S. Length of screen 23'Type of pump Byron Jackson submersibleCapacity of pump 750 GPM @ 350 TDHDepth of pump setting 70'Date of completion 10/20/79**BAILING OR PUMPING TEST**


(specify one by circling)

Test rate 837 gpm Duration of test 24 hrsDrawdown 7.5' ft Date 2/7/80Static level (depth to water) 18'6" ftQuality (clear, cloudy, taste, odor) clearPump installed by Moody's of Dayton

WELL # 51

WELL LOG*

Formations: sandstone, shale, limestone, gravel, clay	From	To
Top soil	0 ft	5 ft
Brown clay	5	15
Brown clay & gravel	15	25
Large gravel	25	35
Small gravel	35	40
Fine sand w/gravel	40	45
Med gravel & fine sand	45	60
Fine sand	60	62
Coal	62	63
Fine sand	63	65
Medium gravel w/boulders	65	90
Shale	90	

SKETCH SHOWING LOCATIONLocate in reference to numbered
state highways, street intersections, county roads, etc.DRILLING FIRM Moody's of Dayton, Inc.DATE June 27, 1980ADDRESS 4359 Infirmary Rd., P.O. Box 123
Miamisburg, Ohio 45342SIGNED [Signature]

*If additional space is needed to complete well log, use next consecutive numbered form.

County Permit No.

WEL' LOG AND DRILLING REPORT

ORIGINAL

NO CARBON PAPER
NECESSARY -
SELF-TRANSCRIBINGState of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
Fountain Square
Columbus, Ohio 43224

547528

COUNTY Hamilton TOWNSHIP Miami ? SECTION OF TOWNSHIP _____OWNER E. I. duPont de Nemours & Company ADDRESS North Bend, Ohio

County Permit No.

WEL' LOG AND DRILLING REPORT

ORIGINAL

NO CARBON PAPER
NECESSARY -
SELF-TRANSCRIBINGState of Ohio
DEPARTMENT OF NATURAL RESOURCES
Division of Water
Fountain Square
Columbus, Ohio 43224

547529

COUNTY Hamilton TOWNSHIP Miami ? SECTION OF TOWNSHIP _____OWNER E. I. duPont de Nemours & Company ADDRESS North Bend, OhioLOCATION OF PROPERTY East of the confluence of the Ohio & Great Miami Rivers**CONSTRUCTION DETAILS**Casing diameter 20" Length of casing 58'
Type of screen 36 x 20 gp s.s. Length of screen 25'
Type of pump Byron Jackson submersible
Capacity of pump 750 GPM @ 350 TDH
Depth of pump setting 70'
Date of completion 3/5/80**BAILING OR PUMPING TEST**

(specify one by circling)

Test rate 1000 gpm Duration of test 24 hrs
Drawdown 11' ft Date 5/29/80
Static level (depth to water) 11'5" ft
Quality (clear, cloudy, taste, odor) clear

Pump installed by _____

WELL # 50

WELL LOG*

Formations: sandstone, shale, limestone, gravel, clay	From	To
Top soil	0 ft	5 ft
Sandy clay	5	25
Grey clay & some gravel	25	30
Grey clay	30	35
Grey clay & med. gravel	35	40
Fine sand & med. gravel	40	60
Coarse gravel	60	70
Coarse gravel & fine sand	70	75
Medium gravel	75	80
Coal seam	80	81
Bedrock	81	85

SKETCH SHOWING LOCATIONLocate in reference to numbered
state highways, street intersections, county roads, etc.